

Minutes

Of the meeting of the:

Strathfield Local Planning Panel Meeting

Held on:

Thursday, 3 September 2020

Commencing at 10:00am at Town Hall (Supper Room),
65 Homebush Road, Strathfield

TABLE OF CONTENTS

Item	Page No.
SLPP AGENDA ITEMS	
SLPP - Report No. 32	
DA2018/001/02 - 32 Courallie Avenue, Homebush West	
Lot 16 DP 11427	4
SLPP - Report No. 33	
DA2020/112: 56 Churchill Avenue, Strathfield	
Lot 1 DP 913096	43
SLPP - Report No. 34	
DA2020/081: 74-76 Homebush Road, Strathfield	
Lot 2 DP4508	57
SLPP - Report No. 35	
DA2020/093 - 25 Rochester Street - Lot 22 DP 527225.....	75

The meeting of the Strathfield Local Planning Panel Meeting was held in the Town Hall (Supper Room), 65 Homebush Road, Strathfield on Thursday 3 September 2020.

The meeting commenced at 10:00am and closed at 12.15pm.

The Public Meeting commenced at 10.03am and closed at 10.45am.

The Panel Members conducted site inspections for the purpose of considering items included on the Agenda-

Site inspection time commenced: Panel members independently conducted site visits

Site inspection time concluded: Panel members independently conducted site visits

PRESENT

Paul Stein – Chair

Jan Murrell – Expert- Not present between 11:00am- 12:00pm

Mr Eric Armstrong – Expert

Mr David Starr - Community

ALSO PRESENT

Stephen Clements, Deputy CEO/General Manager Planning, Environment & Urban Services

Kandace Lindeberg, Executive Manager, Landuse Planning & Development

Sarah Evans, Administration Assistant

Joseph Gillies, Senior Planner

DECLARATIONS OF PECUNIARY INTEREST / CONFLICT OF INTEREST

Nil

TO: Strathfield Local Planning Panel Meeting - 3 September 2020
REPORT: SLPP – Report No. 32
SUBJECT: DA2018/001/02 - 32 COURALLIE AVENUE, HOMEBUSH WEST
 LOT 16 DP 11427
DA NO. DA2018/001/02

RECOMMENDATION

Pursuant to Section 4.56 of the Environmental Planning and Assessment Act 1979, the proposed modifications to Development Consent No. 2018/001 involving internal and external reconfiguration, revising of external finishes and amendments to conditions of consent of an approved boarding house at 32 Courallie Avenue, Homebush West be **APPROVED**, subject to:

1. The original conditions of consent of Development Application No. (DA2018/001) as approved by the Land and Environment Court of NSW on 14 February 2019;
2. As modified by the Section 4.56 modification application (DA2018/001/02) as follows:
 - Modification of development description to correct description error;
 - Modification of Condition No. 1 to reflect the amended plans and documents;
 - Modification of Condition No. 2 to reflect the modified maximum number of residents;
 - Modification Condition No. 3 to reflect the modified building height;
 - Deletion of Condition No. 8 to correct error;
 - Modification of Condition No. 10 relating to tree removal;
 - Addition of Condition No. 10A to ensure the existing street tree is retained;
 - Modification of Condition No. 13 relating to canopy tree planting;
 - Modification of Condition No. 28 relating to driveway requirements;
 - Modification of Condition No. 33 relating to driveway requirements;
 - Deletion of Condition No. 38 relating to driveway requirements;
 - Modification of Condition No. 66 relating to waste collection;
 - Addition of Condition No. 50C relating to laundry noise;
 - Modification of Condition No. 63 relating to waste collection;
 - Modification of Condition No. 66 relating to waste collection;
 - Addition of Condition No. 69A relating to the fire hydrant;
 - Deletion of Condition No. 74 to correct error;
 - Addition of Condition No. 96B relating to the water and gas meters;
 - Modification of Condition No. 91 relating to waste collection; and
 - Deletion of Condition No. 93 relating to waste collection.

Accordingly, Development Consent No. DA2018/001/02 is approved as following:

Development Description:

Demolition of existing structures and construction of a four (4) storey boarding house containing(15) lodger rooms and one (1) manager's room

GENERAL CONDITIONS (GC)

1. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No.2018/001/01:

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
A050	Site Plan	Enhance Group Project Pty Ltd	Rev D, 28 May 2020	18 August 2020
A060	Demolition Plan	Enhance Group Project Pty Ltd	Rev B, 28 May 2020	18 August 2020
A100	Basement 1	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A101	Ground Floor Plan	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A102	Level 1	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A103	Level 2	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A104	Level 3	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A105	Roof	Enhance Group Project Pty Ltd	Rev H, 14 August 2020	18 August 2020
A300	Elevation - North	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A301	Elevation - South	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A302	Elevation - West	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A303	Elevation - East	Enhance Group Project Pty Ltd	Rev B, 18 August 2020	18 August 2020
A400	Section 1 - Long	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A401	Section 2 – Long - Driveway	Enhance Group Project Pty Ltd	Rev G, 18 August 2020	18 August 2020
A402	Section 3 & 4 - Short	Enhance Group Project Pty Ltd	Rev F, 18 August 2020	18 August 2020
A403	Section 5 - Short	Enhance Group Project Pty Ltd	Rev F, 18 August 2020	18 August 2020
A500	Privacy Study	Enhance Group Project Pty Ltd	Rev A, 2 July 2020	18 August 2020

MODIFIED: DA2018/001/02 3 September 2020

Reference Documentation affixed with Council's 'Development Consent' stamp relating to Development Consent No.2018/001/01:

Title / Description	Prepared by	Issue/Revision & Date	Date received by Council
Traffic and Parking Impacts Report	TEF Consulting	Dated 12 April 2018	12 December 2018
Arboricultural Impact Assessment	Lee Hancock Consulting Arborist	Dated 27 March 2018	12 December 2018
Plan of Management	Nexus Environmental Planning Pty Ltd	Dated 18 December 2018	19 December 2018
BASIX Certificate	No. 990654M_03	Issued 18 August 2020	20 August 2020

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

MODIFIED: DA2018/001/02 3 September 2020

2. **BOARDING HOUSE - APPROVED USE (GC)**

- The boarding house must be operated in accordance with the Boarding Houses Act 2012.
- The boarding house is required to be registered on a register administered by NSW Fair Trading within 28 days where a proprietor takes over an existing, or begins operating a new, registrable boarding house.

Council will carry out initial (within the first 12 months) and ongoing inspections in accordance with the Boarding Houses Act 2012 subject to payment of inspection fees as detailed in Council's Fees and Charges schedule.

- The boarding house is to comply with the approved Plan of Management required by this consent.
- The use of the premises as a boarding house must comply always with the following:
 - a) A copy of the Plan of Management and House Rules must be annexed to every tenancy/occupation agreement for a room;
 - b) A copy of the approved Plan of Management and House Rules must be clearly displayed within the common room in the building at all times;
 - c) All tenancy/occupation agreements for rooms within the premises must be for a minimum period of three (3) months;
 - d) The premises must be used exclusively as a boarding house containing a maximum total of **19** residents, with one (1) lodger permitted per single room and two (2) lodgers per double room, in accordance with the approved floor plans;
 - e) The premises must not be adapted for use as backpacker's accommodation, serviced apartments or a residential flat building;
 - f) All common rooms/areas and recreation rooms/areas must be maintained at all times for the use of the lodgers;
 - g) Each self-contained room be fitted out with washing up facilities, a cooktop, microwave oven, fridge and storage space with such utilities being maintained in working order at all times;
 - h) All rooms within the boarding house must be connected to a centralised electricity, water and gas (if installed) service and room tariffs must not include a separate charge for these services; and
 - i) The communal room shall be provided with an oven and cooktop.
 - j) The Plan of Management is to be amended to include the provisions of the use of the laundry facility and must not be used between 9pm and 7am Monday-Sunday.**
- The Plan of Management must be updated to reflect the requirements outlined within this condition.
- Any proposed amendments to the Management Plan are to be submitted to Council for consideration and approval prior to any amendments being made.

- If the operator of the boarding house alters from the operator nominated in the Plan of Management, a new Plan of Management is to be submitted to Council within 28 days of the change in operator unless it is confirmed in writing that the new operator will comply with the Plan of Management approved as part of this consent.

(Reason: To ensure the development is the permanent place of residence for occupants and ensure occupants abide by the rules and regulations identified in the Plan of Management and that the Plan of Management, if amended meets the objectives of this condition, to the satisfaction of Council.)

MODIFIED: DA2018/001/02 3 September 2020

3. **BUILDING HEIGHT - MAXIMUM RL TO BE COMPLIED WITH (GC)**

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) **23.50AHD to the lift overrun of the building.**

(Reason: To ensure the approved building height is complied with.)

MODIFIED: DA2018/001/02 3 September 2020

4. **CONSTRUCTION HOURS (GC)**

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

5. **CONSTRUCTION WITHIN BOUNDARIES (GC)**

The development including but not limited to footings, walls, roof barges and guttering must be constructed wholly within the boundary of the premises. No portion of the proposed structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath or adjoining land.

(Reason: Approved works are to be contained wholly within the subject site.)

6. **DEMOLITION – GENERALLY (GC)**

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

7. **DEMOLITION - SITE SAFETY FENCING (GC)**

Site fencing is to be erected to a minimum height of 1.8m complying with WorkCover Guidelines, to exclude public access to the site, prior to any demolition works occurring and

maintained for the duration of the demolition works.

If applicable, a separate Hoarding Application for the erection of an A class (fence type) or B class (overhead type) hoarding/fencing along the street frontage(s) complying with WorkCover requirements must be obtained including:

- Payment to Council of a footpath occupancy fee based on the area of footpath to be occupied and Council's Schedule of Fees and Charges before the commencement of work; and
- Provision of a Public Risk Insurance Policy with a minimum cover of \$10 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy provided to Council.

(Reasons: Statutory requirement and health and safety.)

8. **DELETED: DA2018/001/02 3 September 2020**

9. **LANDSCAPING - IRRIGATION OF COMMON AND PRIVATE LANDSCAPE AREAS (GC)**

All common and private landscape areas including all planters of new multi-unit, commercial, mixed-use and industrial development are to have full coverage by a fully automatic irrigation system. The design, materials and installation are to be in accordance with Sydney Water Codes and satisfy all relevant Australian Standards. Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior occupation of the premises.

(Reason: To ensure appropriate landscape maintenance.)

10. **LANDSCAPING - TREES PERMITTED TO BE REMOVED (GC)**

The following listed trees are permitted to be removed to accommodate the proposed development:

Tree No. in Arborist Report	Tree	Location
Tree No. 1	Citrus spp.	Rear yard
Tree No. 2	Citrus spp.	Rear yard
Tree No. 3	Prunus spp.	Rear yard
Tree No. 4	<i>Ricinus communis</i> (caster oil plant)	Rear yard

MODIFIED: DA2018/001/02 3 September 2020

10A. **LANDSCAPING – TREES FOR RETENTION (GC)**

The trees listed below shall be retained at all times:

Tree	Height	Location
Lophostemon confertus (Brush box)	6m	Road Reserve

(Reason: To ensure the protection of trees to be retained on the site.)

ADDED: DA2018/001/02 3 September 2020

11. ENVIRONMENTAL PROTECTION – TREE (GC)

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Section 4, Tree protection measures, and Appendix C Tree Protection Zone Sign, of Australian Standard AS4970 - 2009, Protection of Trees on Development Sites, prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

In this regard the street tree and all protected trees on or adjacent to the site will be protected as described below;

- i. A Tree Protection (Management) Plan prepared by a AQF Level 5 Arborist is to be available on site at all times prior to the issue of the Constriction Certificate, for all demolition and site works. This Tree Protection (Management) Plan must be shown on the demand of Authorised Council staff.
- ii. Protective perimeter fencing must be consistent with AS 4687, using metal fence posts greater than 20mm diameter and solid or chain wire mesh 2 metres in height supported on concrete pads/feet at 2-2.5 metre spacing. Fencing placement should not be closer than 2.5 metres from the trunk of each protected tree, or at a distance as specified by the approved Tree Protection (Management) Plan and approved by Council's Tree Management Officer. Shade cloth is to be used to prevent entry of dust and contaminated liquids into the root protection area.
- iii. Signs must be placed on the Fencing. These signs must comply with AS1319. The signs must state the purpose of the fencing and the name and contact details of the builder and the appointed AQF Level 5 consultant arborist.
- iv. Root protection is to be provided in the form of mulching to a depth of 50-100mm, inside of the fenced tree protection zone.
- v. Ground (Root) Trunk and Branch Protection must comply with the diagram of Figure 4 of AS4970 – 2009. Ground protection within the tree protection zone and drip line should be in the form of heavy steel plates or timber rumble boards over mulch or aggregate. Trunk and branch protection should be to a minimum height of 2 metres and must include measures to protect the tree/s against damage from the movement of trucks, plant equipment and materials at greater heights above ground level.
- vi. Temporary signs, cables, wires must not be attached to, or suspended, on any street tree or protected tree.
- vii. Above ground utilities must not be placed within the canopy of an existing protected tree, or create the future need for clearance pruning.
- viii. Below ground utilities/services must not be located inside the fenced tree protection zone.
- ix. Scaffolding must not be located in the fenced tree protection zone unless authorised by the approved Tree Protection (Management) Plan and Council's Tree Management Officer
- x. Council must be notified in writing within 24 hours, for all temporary removal of the tree protection fencing ground (root) trunk and branch protection within the root protection area.
- xi. Pruning of a street tree is prohibited without the written consent of Council.

(Reason: To ensure the protection of trees to be retained on the site.)

12. LANDSCAPING - CANOPY TREES IN FRONT YARD (GC)

New development shall provide at least two (2) canopy trees within the front setback adjacent the front boundary. New canopy trees shall be planted from 200 litre containers at the time of planting and capable of reaching a potential mature height of 6m.

The new trees must not be planted closer than 1.5 metres from a structure or property boundary.

Species shall be selected from Council's Recommended Tree List (Available from Council's website or from the Customer Service Centre). Compliance with this condition is to be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

Trees are to conform to the NATSPEC guide and Guide for assessing the quality of and purchasing of landscape trees by Ross Clarke, 2003. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting; and shall be maintained until maturity.

All trees are to be staked and tied with a minimum of three (3) hardwood stakes. Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.

Soil conditioner/fertilizer/moisture retention additive/s are to be applied in accordance with manufacturer's recommendations, and mixed into the backfilling soil after planting tree/s.

A minimum 75mm depth of organic mulch shall be placed within an area 0.5m from the base of the tree.

Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure the landscape character of the locality is maintained.)

13. LANDSCAPING – CANOPY TREES IN REAR YARD (GC)

New development shall provide at least two (2) canopy trees. New canopy trees shall be planted from 200 litre containers at the time of planting and capable of reaching a potential mature height of 6m.

Species shall be selected from Council's Recommended Tree List (Available from Council's website or from the Customer Service Centre). Compliance with this condition is to be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

Trees are to conform to the NATSPEC guide and Guide for assessing the quality of and purchasing of landscape trees by Ross Clarke, 2003. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting; and shall be maintained until maturity.

All trees are to be staked and tied with a minimum of three (3) hardwood stakes. Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.

Soil conditioner/fertilizer/moisture retention additive/s are to be applied in accordance with manufacturer's recommendations, and mixed into the backfilling soil after planting tree/s.

A minimum 75mm depth of organic mulch shall be placed within an area 0.5m from the base of the tree.

Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure the landscape character of the locality is maintained.)

MODIFIED: DA2018/001/02 3 September 2020

14. LIGHTING (GC)

Any lighting of the premises shall be installed and maintained in accordance with Australian Standard AS 4282-1997: Control of the Obtrusive Effects of Outdoor Lighting so as to avoid annoyance to the occupants of adjoining premises or glare to motorists on nearby roads.

No flashing, moving or intermittent lighting, visible from any public place may be installed on the premises or external signage associated with the development, without the prior approval of Council.

(Reason: To protect the amenity of surrounding development and protect public safety.)

15. MATERIALS – CONSISTENT WITH SUBMITTED SCHEDULE (GC)

All external materials, finishes and colours are to be consistent with the schedule submitted and approved by Council with the development application.

(Reason: To ensure compliance with this consent.)

16. PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) the Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) the Principal Contractor by showing the Principal Contractor's name, address and telephone number (outside of work hours) for that person; and
- iii) the sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

17. PRIVACY - SCREEN PLANTING TO SIDE AND REAR BOUNDARIES (GC)

Evergreen shrubs with a minimum 5 litre container size achieving a minimum mature height of 3m shall be planted along the side and rear boundaries to provide suitable privacy screening. Screen planting shall be maintained at all times. Details of the selected plants shall be submitted to and approved by the Principal Certifying Authority. Compliance with this condition shall be certified by the Principal Certifying Authority, prior to occupation of the premises.

(Reason: To maintain privacy amenity to neighbouring residences.)

18. SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. Protection pads are to be installed to the kerb, gutter and nature strip where trucks and vehicles enter the site.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- x) All waste must be contained entirely within the site.
- xi) A site plan including temporary waste storage locations, construction material storage areas and vehicular access to and from the site must be included with application.
- xii) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling and must be presented to Council and/or Principal Certifying Authority upon request.
- xiv) All materials on site or being delivered to the site are to generally be contained within the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.
- xv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
- xvi) Public footways, include nature strips and roadways adjacent to the site must be

maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.

- xvii) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
- xviii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
- xix) Any work must not prohibit or divert any natural overland flow of water.
- xx) Toilet facilities for employees must be provided in accordance with WorkCover NSW.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

19. **STORMWATER MANAGEMENT PLAN - CERTIFICATION REQUIREMENT (GC)**

A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by an Accredited Civil/Hydraulic Engineer and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

20. **SYDNEY WATER – STAMPED PLANS PRIOR TO COMMENCEMENT (GC)**

The approved plans must be submitted to a Sydney Water Quick Check agent or Customer Centre to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Plans will be appropriately stamped.

For Quick Check agent details refer to the web site www.sydneywater.com.au (see Building Developing and Plumbing then Quick Check or telephone 13 20 92. The consent authority or a Certifying Authority must ensure that a Quick Check agent/Sydney Water has stamped the plans before the commencement of work.

(Reason: Compliance with Sydney Water requirements.)

21. **UTILITIES AND SERVICES - PROTECTION OF (GC)**

Any footings or excavation to be located or undertaken adjacent to Council's stormwater must be designed to address the following requirements:

- i) all footings and excavation must be located wholly within the site and clear of any easement boundaries;
- ii) all footings and excavation must be located a minimum of 1000mm from the centreline of the pipeline or 500mm from the outside of the pipeline, whichever is the greater distance from the centreline; and
- iii) footings must extend to at least the depth of the invert of the pipeline unless the footings are to be placed on competent bedrock.

If permanent excavation is proposed beneath the obvert of the pipeline, suitable means to

protect the excavation and proposed retaining structures from seepage or other water flow from the pipeline and surrounding subsoil, must be provided. The design must be prepared by a qualified practicing Structural/Civil Engineer.

Construction plans must be approved by the appropriate utility's office (e.g. council, Sydney Water Corporation) to demonstrate that the development complies with the utility's requirements.

The applicant must provide written evidence (e.g. compliance certificate, formal advice) of compliance with the requirements of all relevant utility providers (e.g. Water, Energy, Telecommunications, Gas).

(Reason: To ensure protection of Council assets.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (CC)

22. ACCESS - ACCESS FOR PEOPLE WITH DISABILITIES (CC)

Access for people with disabilities must be provided in accordance with the requirements of the Building Code of Australia, relevant Australian Standards and with regard to the Disability Discrimination Act 1992. Plans shall be notated demonstrating compliance and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

Note: Disability (Access to Premises - Buildings) Standards 2010 - As of 1 May 2011, if access is provided to the extent covered by this Standard, then such access cannot be viewed as unlawful under the Disability Discrimination Act 1992.

(Reason: To provide equitable access for people(s) with disabilities in accordance with the relevant legislation and Australian Standards.)

23. ACCESS - DISABLED TOILETS (CC)

Plans and details of the disabled toilet/s complying with the relevant Australian Standards, the Building Code of Australia, and with regard to the Disability Discrimination Act 1992. Plans shall be notated demonstrating compliance and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

Note: Disability (Access to Premises - Buildings) Standards 2010 - As of 1 May 2011, if access is provided to the extent covered by this Standard, then such access cannot be viewed as unlawful under the Disability Discrimination Act 1992.

(Reason: To provide equitable access for people(s) with disabilities in accordance with the relevant legislation and Australian Standards.)

24. BASIX COMMITMENTS (CC)

The approved BASIX Certificate shall be submitted to the Principal Certifying Authority with the application for a Construction Certificate.

Where a change or changes are proposed in the BASIX commitments, the applicant must submit a new BASIX Certificate to the Principal Certifying Authority and Council. If any proposed change in the BASIX commitments is inconsistent with the development consent the applicant will be required to submit a modification to the development consent to Council under Section 4.55 of the Environmental Planning and Assessment Act 1979.

All commitments in the BASIX Certificate must be shown on the plans accompanying the Construction Certificate.

(Reason: Statutory compliance.)

25. BICYCLE STORAGE PROVISION (CC)

On-site provision for bicycle storage facilities shall be in accordance with the Strathfield Consolidated Development Control Plan 2005. Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance with SCDCP 2005 and to encourage sustainable transport options.)

26. BOARDING HOUSE - CONSTRUCTION OF (CC)

The construction of the boarding house shall comply with all applicable legislation/regulation and standards, including:

- i) Boarding Houses Act 2012;
- ii) Boarding Houses Regulation 2013;
- iii) Local Government Act 1993; and
- iv) Local Government Regulation 2005.

Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior to occupation of the premises.

(Reason: To ensure compliance with relevant legislation.)

27. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

28. CAR PARKING - BASEMENT CAR PARKING REQUIREMENTS (CC)

Details demonstrating compliance with the following is to be submitted to the Principal Certifying Authority, prior to issue of the Construction Certificate:

- i) Minimal internal clearance of the basement is 2.2m in accordance with BCA requirements.
- ii) Driveways shall comply with Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking and achieve a maximum gradient of 1:4.

iii) DELETED

- iv) Provision of pump-out systems and stormwater prevention shall be in accordance with Council's Stormwater Management Guide.

(Reason: To ensure suitable development.)

MODIFIED: DA2018/001/02 3 September 2020

29. CAR PARKING - DISABLED CAR PARKING SPACES (CC)

One (1) of the car parking spaces provided as part of the total requirement shall be reserved for disabled persons. These spaces shall be a minimum of 2.4m wide x 5.4m long and located near pedestrian access routes designed for disabled persons. Each space shall be clearly marked as such. A shared area 2.4 m wide x 5.4m long shared area should be provided. Bollard shall be placed in this shared area.

Car parking for people with disabilities shall be provided in accordance with the Building Code of Australia, relevant Australian Standards and with regard to the Disability Discrimination Act 1992. Prior to the issue of a Construction Certificate, the plans shall be notated to demonstrate compliance.

The above details shall be submitted to and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate.

(Reason: To ensure adequate parking for persons with a disability.)

30. CAR PARKING - VEHICULAR ACCESS RAMPS (CC)

Vehicular access ramps shall comply with the provisions of AS/NZS 2890.1:2004. Plans to be submitted shall contain the following details:

- i) Longitudinal section along the extreme wheel paths of each driveway/access ramp at a scale of 1:25 demonstrating compliance with the scraping provisions of AS/NZS 2890.1:2004. It shall include all levels and grades, including those levels stipulated as boundary levels, both existing and proposed. It shall extend from the centre-line of the roadway through to the parking area.
- ii) Sections showing the clearance to the underside of any overhead structure (minimum headroom requirements 2200mm minimum for standard headroom clearance or 2400mm where disabled access provisions are to be provided) demonstrating compliance with the provisions of AS/NZS 2890.1:2004.
- iii) Longitudinal section along the gutter line showing how it is intended to transition the vehicular crossing into the existing kerb and gutter. Boundary levels shall generally run parallel with the kerb levels.
- iv) Location of verge trees, street furniture and service installations.
- v) Superimposition of vehicle turning circles for access into parking spaces.
- vi) Certification that the design complies with AS/NZS 2890.1:2004 by a Qualified Engineer.

The certification referred to in (vi) above shall be submitted to the Principal Certifying Authority prior to the issue of a Construction Certificate (for the design) and to the Principal Certifying Authority prior to the issue of any Occupation Certificate for the 'as-built works'.

(Reason: To ensure adequate vehicular access can be achieved.)

31. CAR PARKING - COMPLIANCE WITH AS/NZS 2890.1:2004 (CC)

Car parking dimensions must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure compliance with Australian Standards relating to parking of vehicles.)

32. **CAR PARKING - VEHICULAR CIRCULATION, AISLE AND RAMP WIDTHS (CC)**

The aisle widths, internal circulation, ramp widths and grades of the car park shall comply with the Roads and Traffic Authority Guidelines and AS/NZS 2890.1:2004 - Off-Street Car Parking Code.

Vehicular manoeuvring paths are to be prepared demonstrating that all vehicles can enter or depart the site in a forward direction without encroaching on required car parking spaces.

(Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.)

33. **CAR PARKING - VEHICULAR CROSSING WIDTH AT PROPERTY BOUNDARY (CC)**

Vehicular crossings are to have a maximum width of **4m** at the property boundary. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

The vehicular crossing (and all associated excavation works) must not be constructed closer than 2 metres from a retained protected street tree.

The relocation of the existing utility pit to accommodate the driveway crossing shall be at no cost to Council.

(Reason: Compliance with SCDCP 2005.)

MODIFIED: DA2018/001/02 3 September 2020

34. **COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)**

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 4.19 of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

35. **CONSTRUCTION AND ENVIRONMENTAL MANAGEMENT PLAN (CC)**

The applicant must prepare and submit a Construction and Environmental Management Plan (CEMP) to the Principal Certifying Authority, including:

- i) Detailed information on any approvals required from other authorities prior to or during construction.
- ii) Traffic management, including details of:
 - ingress and egress of vehicles to the site;

- management of loading and unloading of materials;
 - the location of heavy vehicle parking off-site; and
 - designated routes for vehicles to the site.
- iii) The proposed areas within the site to be used for a builder's site office and amenities, the storage of excavated material, construction materials and waste containers during the construction period.
- iv) Erosion and sediment control, detailing measures and procedures consistent with the requirements of Council's guidelines for managing stormwater, including:
- the collection and treatment of stormwater and wastewater generated on site prior to discharge; and
 - procedures to prevent run-off of solid material and waste from the site.
- v) Waste management, including:
- details of the types and estimated volumes of waste materials that will be generated;
 - procedures for maximising reuse and recycling of construction materials; and
 - details of the off-site disposal or recycling facilities for construction waste.
- vi) Dust control, outlining measures to minimise the generation and off-site transmission of dust and fine particles, such as watering or damp cloth fences.
- vii) A soil and water management plan, which includes:
- measures to minimise the area of soils exposed at any one time and conserve top soil;
 - identification and protection of proposed stockpile locations;
 - preservation of existing vegetation and revegetation;
 - measures to prevent soil, sand, sediments leaving the site in an uncontrolled manner;
 - measures to control surface water flows through the site in a manner that diverts clean run-off around disturbed areas, minimises slope gradient and flow distance within disturbed areas, ensures surface run-off occurs at non-erodible velocities, and ensures disturbed areas are promptly rehabilitated;
 - details of sediment and erosion control measures in place before work commences;
 - measures to ensure materials are not tracked onto the road by vehicles entering or leaving the site; and
 - details of drainage to protect and drain the site during works.
- viii) Asbestos management procedures:
- Anyone who removes, repairs or disturbs bonded or a friable asbestos material must hold a current removal licence from Workcover NSW holding either a Friable (Class A) or a Non- Friable (Class B) Asbestos Removal License which ever applies and a current WorkCover Demolition License where works involve demolition. To find a licensed asbestos removalist please see www.workcover.nsw.gov.au
 - Removal of asbestos by a person who does not hold a Class A or Class B asbestos removal license is permitted if the asbestos being removed is 10m² or less of non-friable asbestos (approximately the size of a small bathroom). Friable asbestos materials must only be removed by a person who holds a current Class A asbestos license.
 - Before starting work, a work site-specific permit approving each asbestos project must be obtained from WorkCover NSW. A permit will not be granted without a current WorkCover licence. All removal, repair or disturbance of or to asbestos material must comply with the following:
 - The Work Health and Safety Act 2011;
 - The Work Health and Safety Regulation 2011;
 - How to Safely Remove Asbestos Code of Practice – WorkCover 2011; and
 - Safe Work Australia Code of Practice for the Management and Control of Asbestos in the Workplace.

- Following completion of asbestos removal works undertaken by a licensed asbestos removalist re-occupation of a workplace must not occur until an independent and suitably licensed asbestos removalist undertakes a clearance inspection and issues a clearance certificate.
- The developer or demolition contractor must notify adjoining residents at least two (2) working days (i.e. Monday to Friday exclusive of public holidays) prior to the commencement of asbestos removal works. Notification is to include, at a minimum:
 - the date and time when asbestos removal works will commence;
 - the name, address and business hours contact telephone number of the demolisher, contractor and/or developer;
 - the full name and license number of the asbestos removalist/s; and
 - the telephone number of WorkCover's Hotline 13 10 50
 - warning signs informing all people nearby that asbestos removal work is taking place in the area. Signs should be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs should be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs should be in accordance with AS 1319-1994 Safety signs for the occupational environment for size, illumination, location and maintenance; and
 - appropriate barricades installed as appropriate to prevent public access and prevent the escape of asbestos fibres. Barricades must be installed prior to the commencement of asbestos removal works and remain in place until works are completed.

(Reason: Safety, amenity and protection of public infrastructure and the environment.)

36. **COUNCIL PERMITS – FOR ALL ACTIVITIES ON COUNCIL LAND (CC)**

Works Permit

(as per Section 68 of the Local Government Act 1993 and Section 138 and 139 of the Roads Act 1993)

A Works Permit is required for construction of a vehicular crossing (driveway), new stormwater down pipe connection to kerb and gutter, new footpath and/or stormwater connection. A Works Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Standing Plant Permit

This permit must be applied for where it is intended to park a concrete pump, crane or other plant on the roadway or footpath. A Standing Plant Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Skip Bin Permit

This permit must be applied for if you intend to place a skip bin on the roadway or footpath. A Skip Bin Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Temporary Full or Part Road Closure Permit

This permit must be applied for if you require a full or a part road closure to take place to assist in your construction works. Please use the Works Permit Application Form, which is

available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Hoarding/Fencing Permit

This permit must be applied for if you intend to erect a Class A (fence type) or Class B (overhead type) hoarding/fencing along the street frontage(s). A Hoarding Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Work Zone Permit

This permit must be applied for if you require permanent parking along the kerbside at the front of the site during construction works. A Work Zone Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Ground Anchoring Permit

This permit must be applied for, for the installation of ground anchors under Council's footway/road reserve. It does not cover ground anchors under private properties. A separate approval is required to be obtained from Roads and Maritime Services (RMS) if it is proposed to install ground anchors under a State or Classified Regional Road (please refer to the end of this application form for more information).

(Reason: Council requirement.)

37. DILAPIDATION REPORT - PRE-COMMENCEMENT (CC)

Subject to access being granted, a pre-commencement Dilapidation Report is to be undertaken on all adjoining properties, which in the opinion of a suitably qualified engineer, could be potentially affected by the construction of the project. The Dilapidation Report shall be carried out prior to the issue of a Construction Certificate.

The Dilapidation Report is to be prepared by a suitably Qualified Engineer with current Corporate Membership with the Institution of Engineers, Australia or Geotechnical Practitioner. The report shall include a photographic survey of adjoining properties detailing the physical condition of those properties, both internally and externally, including walls, ceilings, roof, structural members and other such items.

If access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant must demonstrate, in writing, to Council's satisfaction attempts have been made to obtain access and/or advise the affected property owner of the reason for the survey and these attempts have been unsuccessful. Written concurrence must be obtained from Council in such circumstances.

The Report shall cover structural and geotechnical factors likely to arise from the development. A copy of this Report shall be submitted to Council as a record. The person having the benefit of the development consent must, at their own cost, rectify any damage caused to other properties during the construction of the project.

(Reason: To ensure no damage to adjoining properties occurs.)

38. DELETED: DA2018/001/02 3 September 2020

39. EROSION AND SEDIMENTATION CONTROL PLAN (CC)

An Erosion and Sediment Control Plan is to be prepared where construction or excavation activity requires the disturbance of the soil surface and existing vegetation. Details including drawings and specifications must provide adequate measures for erosion and sediment control to ensure:

- i) Compliance with the approved Soil and Water Management Plan.
- ii) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval).
- iii) All uncontaminated run-off is diverted around cleared or disturbed areas.
- iv) Silt fences or other devices are installed to prevent sediment and other debris escaping from the cleared or disturbed areas into drainage systems or waterways.
- v) All erosion and sediment controls are fully maintained for the duration of demolition/development works.
- vi) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadways.
- vii) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar.
- viii) All water pumped or otherwise removed from excavations or basement areas is filtered to achieve suspended solids/non filterable residue levels complying with the Australian Water Quality guidelines for Fresh and Marine Waters.
- ix) Pumped or overland flows of water are discharged so as not to cause, permit or allow erosion before the commencement of work (and until issue of the occupation certificate).

Details of the proposed soil erosion and sedimentation controls are to be submitted to the Principal Certifying Authority with the Construction Certificate Application. Under no circumstances are any works to commence, prior to these details being approved by the Principal Certifying Authority and the controls being in place on the site.

(Reason: Environmental protection.)

40. EXCAVATION - AFFECTING ADJOINING LAND (CC)

If an excavation associated with the approved development extends below the level of the base of the footings of a building on an adjoining allotment of land, the person having the benefit of the development consent must, at the person's own expense, comply with the requirements of clause 98E of the Environmental Planning and Assessment Regulation 2000, including:

- i) Protect and support the adjoining premises from possible damage from the excavation, and
- ii) Where necessary, underpin the adjoining premises to prevent any such damage.

The condition referred to in subclause (i) does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying. Details shall be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Structural safety.)

41. EXCAVATION – DEWATERING (CC)

Any de-watering from the excavation or construction site must comply with the Protection of the Environment Operations Act 1997 and the following:

- i) Ground water or other water to be pumped from the site into Council's stormwater system must be sampled and analysed by a NATA accredited laboratory or Council for compliance with ANZECC Water Quality Guidelines.
- ii) If tested by NATA accredited laboratory, the certificate of analysis issued by the laboratory must be forwarded to Council as the appropriate regulatory authority under the Protection of the Environment Operations Act 1997, prior to the commencement of de-watering activities.
- iii) Council will grant approval to commence site de-watering to the stormwater based on the water quality results received.
- iv) It is the responsibility of the applicant to ensure during de-watering activities, the capacity of the stormwater system is not exceeded, there are no issues associated with erosion or scouring due to the volume of water pumped; and turbidity readings must not at any time exceed the ANZECC recommended 50ppm (parts per million) for receiving waters.

(Reason: To ensure compliance with legislation and to protect the surrounding natural environment.)

42. **EXCAVATION – SHORING (CC)**

Where any shoring for excavation is to be located on or is supporting Council's property, or any adjoining private property, engineering drawings and specifications certifying the shoring will be adequate for their intended purpose and must be submitted to the Council/Principal Certifying Authority for approval with the Construction Certificate. The documentation prepared and certified by an appropriately qualified and practicing structural engineer is to show all details, including the extent of encroachment and the method of removal and de-stressing of shoring elements. A copy of this documentation must be provided to the Council for record purposes at the time of Construction Certificate application.

(Reason: To ensure the protection of existing public infrastructure and adjoining properties.)

43. **FIRE SAFETY SCHEDULE (CC)**

A Fire Safety Schedule specifying the fire safety measures (both current and proposed) which should be implemented in the building premises must be submitted with the Construction Certificate application, in accordance with Part 9 of Clause 168 of the Environmental Planning and Assessment Regulation 2000.

Note: A Construction Certificate cannot be issued until a Fire Safety Schedule is received.

(Reason: Compliance with the Environmental Planning and Assessment Act 1979.)

44. **GEOTECHNICAL REPORT (CC)**

A comprehensive geotechnical engineering report assessing the impact and safety of the proposed works shall be prepared by a suitably experienced and qualified geo-practitioner and submitted with any Construction Certificate. The report must include the results of subsurface investigations involving either test pits to rock, or preferably the drilling of cored boreholes (to 1m below the proposed final excavation level). The report shall provide:

- i) an indication of the nature and depth of any uncontrolled fill at the site;
- ii) an indication of the nature and condition of the material to be excavated;
- iii) indications of groundwater or seepages;
- iv) required temporary measures for support of any excavations deeper than 1m adjacent

- to property boundaries;
- v) a statement of required excavation methods in rock and measures required to restrict ground vibrations; and
- vi) other geo-technical information or issues considered relevant to design and construction monitoring.

(Reason: Structural safety.)

44A. **LANDSCAPING - LANDSCAPE PLAN REQUIRED (CC)**

A landscape plan prepared by a qualified landscape architect or landscape consultant to a scale of 1:100 or 1:200, conforming to all relevant conditions of consent is to be submitted to the satisfaction of the Principal Certifying Authority with the Construction Certificate application.

The plan must include the following information:

- i) details demonstrating compliance with SCDCP 2005 in relation to landscaping requirements;
- ii) location of all existing and proposed landscape features including materials to be used;
- iii) all trees to be retained, removed or transplanted;
- iv) existing and proposed finished ground levels;
- v) top and bottom wall levels for both existing and proposed retaining and free standing walls; and
- vi) a detailed plant schedule which includes proposed species listed by botanical (genus and species) and common names, quantities of each species, pot sizes and the estimated size at maturity. A minimum of 25% of species shall be locally sourced indigenous species. Species shall be predominantly selected from Council's Recommended Tree List.

Consideration within the design should be given to the scale of planting in proportion to the proposed development, consistency with the existing landscape character of the area, potential views, solar access and privacy for neighbouring development.

(Reason: Landscape quality.)

45. **LANDSCAPING - MAINTENANCE STRATEGY (CC)**

To ensure the survival of landscaping following works, a landscape maintenance strategy for the owner/occupier to administer over a 12 month establishment period following the issue of the Occupation Certificate shall be prepared and provided to the satisfaction of the Principal Certifying Authority with the Construction Certificate application. The strategy is to address maintenance issues such as, but not limited to plant survival, irrigation, soil testing, weeding, staking, fertilizing, remedial pruning and plant replacement.

(Reason: Ensure landscape survival.)

46. **LANDSCAPING ON SLAB (CC)**

To ensure the site landscaping thrives, the on slab landscaping shown on the approved landscaping plan is to be designed to include a minimum soil depth of 650mm for shrubs and trees; and 300mm for grass and ground covers. Adequate drainage provision and a permanent, automatic irrigation system conforming to Sydney Water requirements shall be included. Details demonstrating compliance shall be submitted to the Principal Certifying Authority with the Construction Certificate application.

(Reason: Ensure landscape survival.)

47. NOISE – VIBRATION (CC)

The construction of the development and preparation of the site, including operation of vehicles, must be conducted so as to avoid unreasonable noise or vibration and cause no interference to adjoining or nearby occupations. Special precautions must be taken to avoid nuisance in neighbouring residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

(Reason: Noise attenuation.)

48. NOISE – PLANT (CC)

All works carried out on site during construction/demolition/excavation or earthworks shall comply with the NSW Protection of the Environment Operations Act 1997. Approved and effective silencing measures shall be provided and maintained on all power-operated plant used on site if required.

(Reason: Safety and amenity.)

49. NOISE – CONSTRUCTION CC)

All works carried out on site during construction/demolition/excavation/earthworks shall comply with the NSW Protection of the Environment Operations Act 1997, the Department of Environment and Climate Changes “Interim construction noise guideline” and AS 2436-2010 – “Guide to noise and vibration control on construction, demolition and maintenance sites” for the control of construction noise which specifies that:

- Construction period of 4 weeks and under – The L90 Level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 20 dB(A) at the boundary.
- Construction period greater than 4 weeks but not exceeding 26 weeks – The L90 level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 10 dB(A) at the boundary.
- Construction period exceeding 26 weeks – The L90 level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 5 dB(A) at the boundary.

Should complaints of a noise nuisance be substantiated, Council may require the acoustic treatment of the premises to ensure compliance with the NSW Department of Environment and Climate Changes “Interim construction noise guideline” and AS 2436-2010 – “Guide to noise and vibration control, demolition and maintenance sites” for the control of construction noise. A further acoustic assessment and report will be required to be provided to Council assessing the premises in working order.

(Reason: Noise attenuation.)

50. ACOUSTIC REPORT (CC)

Prior to the issue of the Construction Certificate the person having the benefit of this development consent shall submit a report to Council or a nominated Accredited Certifier from a suitably qualified and practicing acoustic engineer demonstrating that the noise levels within all dwellings in all stages will not exceed the recommended noise levels outlined in The

Australian and New Zealand Standard entitled "AS/NZS 2107, Acoustics – Recommended design sound levels and reverberation times for building interiors".

Road Noise

The Boarding House is to include standard noise control construction treatments in accordance with the NSW Department of Planning publication "Development near Rail Corridors and Busy Roads – Interim Guidelines" Appendix C Acoustic Treatment of Residences in order to ensure the following LAeq levels are not exceeded:

- (a) in any bedroom in the building – 35 dB(A) at any time between 10pm – 7am;
- (b) anywhere else in the building (other than garage, kitchen, bathroom or hallway) – 40 dB(A) at any time.

(Reason: Noise control and amenity.)

50A. **NOISE AND VIBRATION MANAGEMENT PLAN (CC)**

Prior to the issue of a Construction Certificate, a Noise and Vibration Management Plan is to be prepared by a suitably qualified person addressing the likely noise and vibration from demolition, excavation and construction of the proposed development and provided to Council or the Principal Certifying Authority.

The Plan is to identify amelioration measures to ensure the noise and vibration levels will be in compliance with:

- a. Construction noise management levels established using the *Interim Construction Noise Guideline (DECC, 2009)*;
- b. Vibration criteria established using the assessing vibration: *Technical guideline (DEC, 2006)* (for human exposure); and
- c. The vibration limits set out in the German Standard DIN 4150-3: *Structural Vibration-effects of vibration on structures* (for structural damage)

The report that itemises equipment to be used for excavation works. The Plan shall address, but shall not be limited to, the following matters:

- i) identification of activities carried out and associated noise sources;
- ii) identification of potentially affected sensitive receivers, including residences, churches, commercial premises, schools and properties containing noise sensitive equipment;
- iii) determination of appropriate noise and vibration objectives for each identified sensitive receiver;
- iv) noise and vibration monitoring, reporting and response procedures;
- v) assessment of potential noise and vibration from the proposed demolition, excavation and construction activities, including noise from construction vehicles;
- vi) description of specific mitigation treatments, management methods and procedures to be implemented to control noise and vibration during construction;
- vii) construction timetabling to minimise noise impacts including time and duration restrictions, respite periods and frequency;
- viii) procedures for notifying residents of construction activities likely to affect their amenity through noise and vibration; and
- ix) contingency plans to be implemented in the event of non-compliances and/or noise complaints. A register should be kept of complaints received, and the action taken to remediate the issue.

(Reason: To protect acoustic amenity of surrounding properties and the public.)

50B. PRIVACY - OBSCURE GLAZING IN WET AREAS (CC)

All bathroom, ensuite and toilet windows shall be installed with obscure glazing. Plans shall be notated accordingly and details demonstrating compliance submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Privacy amenity.)

50C. ACOUSTIC PRIVACY - LAUNDRY (CC and OC)

Prior to issuing of the Construction Certificate, an acoustic report shall be submitted to Council demonstrating that the design of the walls and the doors to the lodger rooms comply with a minimum 5 star rating in accordance Guideline for Apartment and Townhouse Acoustic Rating by Association of Australasian Acoustical Consultants.

Prior to issuing of an Occupation Certificate, a qualified acoustic engineer to test and certify the acoustic door and wall directly adjacent to the laundry and submit the report to Council for review.

(Reason: To ensure sufficient noise mitigation to reduce the noise transmission impact from the open laundry).

ADDED: DA2018/001/02 3 September 2020

51. ROOF TERRACES GENERALLY (CC)

Roof terraces shall not be visible from the public domain with no direct lines of sight to adjoining private open spaces or habitable window openings both within the development site and within adjoining sites. No permanent structures or furniture shall be erected on the roof terrace, and the roof area outside of the terrace area shall be non-trafficable. Plans shall be notated accordingly and details demonstrating compliance demonstrated to the Principal Certifying Authority, prior to the issue of any Construction Certificate.

Roof terraces shall comply with the Building Code of Australia in respect of any provisions relating to roof terraces.

(Reason: To preserve the amenity of adjoining residences and the public domain.)

52. SECTION 7.11 CONTRIBUTION PAYMENT - DIRECT CONTRIBUTIONS PLAN (CC)

In accordance with the provisions of Section 7.13 of the Environmental Planning and Assessment Act 1979 and the Strathfield Direct Development Contributions Plan 2010-2030, a contribution in the form of cash, cheque or credit card (financial transaction fee applies) shall be paid to Council for the following purposes:

Provision of Community Facilities	\$ 14,439.51
Provision of Major Open Space	\$ 65,695.44
Provision of Local Open Space	\$ 27,789.57
Provision Roads and Traffic Management	\$ 4,794.96
Administration	\$ 1,245.08
TOTAL	\$113,964.56

The total amount of the contribution is valid as at the date of determination and is subject to

quarterly indexation. Contributions shall be indexed at the time of payment in accordance with clause 2.14 of the Strathfield Direct Development Contributions Plan 2010-2030.

Contributions must be receipted by Council and submitted to the Accredited Certifier, prior to the issue of any Construction Certificate.

Please present a copy of this condition when paying the contribution at the Customer Service Centre so that it can be recalculated.

Note: A copy of Strathfield Council's Section 7.11 Direct Development Contributions Plan may be downloaded from Council's website.

(Reason: To enable the provision of public amenities and services required/anticipated as a consequence of increased demand resulting from the development.)

53. **SECURITY PAYMENT – DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)**

A security (damage deposit) of **\$18,000.00** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

(Reason: Protection of Council infrastructure.)

54. **STORMWATER - RAINWATER RE-USE (CC)**

A rainwater re-use system shall be provided in accordance with either the BASIX minimum requirements, any relevant Council Rainwater Policy and/or specification of the management of stormwater, whichever is applicable. A detailed stormwater plan showing the proposed re-use system shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance and amenity.)

55. STORMWATER DRAINAGE (CC)

The following stormwater precautions are required to be provided on the site:

- i) Grated drains shall be provided along the driveway/basement entry at the vehicular crossing(s) and are to connect to the internal drainage system.
- ii) Overflow paths shall be provided to allow for flows in excess of the capacity of the pipe/drainage system draining the site.
- iii) Allowance shall be made for surface runoff from adjacent properties, and to retain existing surface flow path systems through the site. Any redirection or treatment of these flows shall not adversely affect any other properties
- iv) Boundary fencing shall be erected in such a manner as not to interfere with the natural flow of ground and surface water to the detriment of any other party.

(Reason: To ensure the site is drained appropriately and does not interfere with the natural flow of flood waters.)

56. STORMWATER - SILT ARRESTORS AND GROSS POLLUTANT TRAPS (CC)

Silt and gross pollutant traps shall be fitted in all new stormwater pits and designed in accordance with Council's specification for the management of stormwater. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Environmental protection.)

57. TRAFFIC - CONSTRUCTION TRAFFIC MANAGEMENT PLAN (CC)

A Construction Traffic Management Plan (CTMP) is to be prepared by an appropriately qualified Traffic Management Consultant and submitted to and approved by Council's Engineering Section, prior to the commencement of any works including demolition.

The following matters should be addressed in the CTMP (where applicable):

- i) description of the demolition, excavation and construction works;
- ii) site plan/s showing the site, roads, footpaths, site access points and vehicular movements;
- iii) size, type and estimated number of vehicular movements (including removal of excavated materials, delivery of materials and concrete to the site);
- iv) proposed route(s) from the arterial (state) road network to the site and the proposed route from the site back to the arterial road network;
- v) impacts of the work and vehicular movements on the road network, traffic and pedestrians and proposed methods to safely manage pedestrians and construction related vehicles in the frontage roadways;
- vi) any Traffic Control Plans (TCP's) proposed to regulate traffic and pedestrian movements for construction activities (such as concrete pours, crane installation/removal etc.);
- vii) proposed hours of construction related activities and vehicular movements to and from the site;
- viii) current/proposed approvals from other Agencies and Authorities (including Roads and Maritime Services, Police and State Transit Authority);
- ix) any activities proposed to be located or impact upon Council's road, footways or any public place;
- x) measures to maintain public safety and convenience;
- xi) any proposed road and/or footpath closures;
- xii) turning areas within the site for construction and spoil removal vehicles, allowing a

- forward egress for all construction vehicles on the site;
- xiii) locations of work zones (where it is not possible for loading/unloading to occur on the site) in the frontage roadways accompanied by supporting documentation that such work zones have been approved by the Local Traffic Committee and Council;
 - xiv) location of any proposed crane and concrete pump and truck standing areas on and off the site (and relevant approvals from Council for plant on road);
 - xv) a dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
 - xvi) material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected;
 - xvii) on-site parking area for employees, tradespersons and construction vehicles as far as possible;
 - xviii) proposed areas within the site to be used for the storage of excavated material, construction materials and waste and recycling containers during the construction period; and
 - xix) how it is proposed to ensure that soil/excavated material is not transported onto surrounding footpaths and roadways.

(Reason: To mitigate traffic impacts on the surrounding area during the construction period.)

58. **TREE BONDS (CC)**

A tree bond of **\$13,200.00** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

(Reason: To ensure the protection of trees to be retained on Council's Road Reserve.)

59. **UTILITIES AND TELECOMMUNICATIONS - ELECTRICITY CONNECTION (CC)**

Provision must be made for connection to future underground distributions mains. This must be achieved by installing:

- i) An underground service line to a suitable existing street pole; or
- ii) Sheathed underground consumers mains to a customer pole erected near the front property boundary (within 1 metre).

Note: A limit of one (1) pole per site will apply.

Any costs associated with the relocation of the above are at the requestor's expense. Any disturbance to public land as a result of the undergrounding of services shall be restored at

no cost to Council.

Details are to be submitted to the Principal Certifying Authority with the Construction Certificate Application.

(Reason: Environmental amenity.)

60. UTILITIES AND TELECOMMUNICATIONS - TELECOMMUNICATIONS ASSETS (CC)

Provision must be made for relocation of telecommunications network assets including underground placement of any existing aerial cables and infrastructure. Any costs associated with the relocation of the above are at the requestor's expense. Any disturbance to public land as a result of the undergrounding of services shall be restored at no cost to Council.

Details are to be submitted to the Principal Certifying Authority with the Construction Certificate application.

(Reason: To ensure suitable relocation of telecommunications infrastructure if required.)

61. VEHICULAR CROSSINGS - WORKS PERMIT FOR CONSTRUCTION OF (CC)

Full-width, heavy-duty concrete vehicular crossing(s) shall be provided across the footpath at the entrance(s) and/or exit(s) to the site and designed in accordance with Council's guidelines and specifications. In this regard, a Works Permit is to be obtained (available from Council's Customer Services Centre or downloaded from Council's website), and the appropriate fees and charges paid, prior to the lodgement of a Construction Certificate.

(Reason: To ensure appropriate access to the site can be achieved.)

62. VENTILATION SYSTEMS – MECHANICAL (CC)

The mechanical ventilation system is to comply with the following:

- i) The Building Code of Australia;
- ii) Protection of the Environment Operations Act 1997; and
- iii) Australian Standard AS1668-1991.

In addition, odour control measures, such as activated carbon or catalytic oxidisers, must be used to treat ventilation gases prior to discharge. The method of odour control must be designed by a suitably qualified mechanical ventilation engineer.

Details demonstrating compliance with the above are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure the mechanical ventilation system complies with the relevant requirements/standards.)

63. BIN ALLOCATION (CC)

(c) Boarding house developments require waste storage areas.

The development will require the provision of the following waste and recycling facilities:

- Domestic Waste – 5 x 240L mobile bins (**collected weekly**).
- Domestic Recycling – 2 x 240L mobile bins (**collected fortnightly**).

(Reason: To ensure sufficient space and waste collection containers provided.)

MODIFIED: DA2018/001/02 3 September 2020

64. WASTE AND RECYCLING STORAGE ROOMS (CC)

Waste (including grease arrestor rooms) and recycling storage rooms must meet all of the following conditions:

- i) The waste and recycling storage room must be of adequate dimensions to comfortably accommodate the required number of waste and recycling bins
 - 240L bin must have 1.1m² of space per bin
 - 660L bin must have 2.03m² of space per bin
- ii) The layout of the waste and recycling storage room must allow easy unobstructed access to all bins (stacked bin arrangements are not acceptable) and allow the bins to be easily removed for servicing purposes.
- iii) A smooth concrete floor graded and drained to a floor waste connected to the sewer of the Water Board.
- iv) The walls being cement rendered with the intersection of the walls and floor being coved to a radius of not less than 25mm.
- v) The door being close fitting to prevent the access of rats and mice.
- vi) A cold water hose cock being provided for the cleaning of containers and the room itself.
- vii) Ventilation being provided by means of direct connection to the outside air to the satisfaction of Council.
- viii) The ceiling of all waste storage rooms must be constructed of a rigid smooth faced non-absorbent material. The ceiling must be a minimum of 2.4m high to accommodate Councils standard bins. This enables access for use, cleaning and enables the lids of bins to be fully opened.
- ix) Contain a sign, minimum size 600mm x 600mm, directing residents not to place recyclables in garbage carts and encouraging residents to recycle. Sample artwork and signs available from Council.
- x) Arrangements must be in place regarding the regular maintenance and cleaning of waste management facilities.
- xi) A caretaker or individual(s) shall be nominated as being responsible for transferring the bins to the collection point and back into the waste storage room/area.
- xii) Detailed plans of waste and recycling storage rooms must be submitted along with Waste Management Plan and Waste and Recycling Storage Room/Area Design Checklist.

(Reason: To keep garbage rooms in a clean and sanitary condition to protect public health.)

65. BULKY WASTE STORAGE (CC)

A store room for storage of bulky household waste such as lounges is to be provided which meets the following conditions:

- i) Bulky waste rooms/areas must be a minimum of 4m² per 10 dwellings.
- ii) Bulky waste (Clean Up) rooms/areas should be located adjacent to waste and recycling storage rooms.
- iii) Bulky waste rooms/areas must contain a sign, minimum size 600mm x 600mm, directing residents the types of waste which can be deposited and the collection process. Sample artwork and signs available from Council.

(Reason: To ensure hard waste is separated and collected efficiently.)

66. ONSITE WASTE COLLECTION (CC)

Onsite waste and recycling collection is to be provided by a private contractor. Bins are prohibited from being presented kerbside for collection. Evidence of a written agreement between the applicant and a private waste contractor for the collection and disposal of waste and recyclables generated from the premises must be submitted and approved by Council's Waste Officer prior to the issue of a Construction Certificate.

Evidence that all relevant standards are satisfied with regards to waste collection in terms of vehicular manoeuvrability, minimum vehicle access requirements and the ability for the waste collection vehicle to exit the site in a forward direction (including the use of mechanical equipment).

An updated Waste Management Plan including a plan of the path of travel of the waste collection vehicle, frequency of collection and bin requirements must be included in the boarding house Plan of Management.

(Reason: To ensure an efficient and effective collection system.)

MODIFIED: DA2018/001/02 3 September 2020

67. WASTEWATER CONTROL (CC)

The applicant shall contact Sydney Water, to determine the requirements for the disposal of wastewater and liquid trade waste (including grease traps or grease arrestors). The applicant must provide a copy of the Authority to connect to the sewer system prior to the issue of a Construction Certificate.

There is to be no discharge of wastewater to the stormwater system.

(Reason: To ensure suitable disposal of waste water.)

68. WATER SUSTAINABILITY – GENERALLY (CC)

Water collected in the rainwater tank must comprise roof water only and not surface water. Water from the rainwater tank must only be used for following purposes and not for human consumption:

- i) toilet flushing;
- ii) clothes washing;
- iii) garden irrigation;
- iv) car washing and similar outdoor uses;
- v) filling swimming pools, spa pools and ornamental ponds; and
- vi) fire fighting.

(Reason: To promote sustainable water management practice.)

69. WATER HEATING SYSTEMS - LOCATION OF (CC)

Water heating systems shall be located so as not to be visible from public places and the ground level of adjoining properties. Details (type and location) of the water heaters shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To maintain streetscape character.)

69A. ENCLOSURE OF FIRE HYDRANT (CC)

Prior to the issue of a construction certificate the certifying authority is to be provided with plans indicating that all fire hydrant and sprinkler booster valves and the like are enclosed in accordance with the requirements of AS2419.1 2005.

(Reason: To protect the appearance of the streetscape)

ADDED: DA2018/001/02 3 September 2020

69B. WATER AND GAS METERS (CC)

An amended landscaped plan is to be submitted to the principal certifying authority prior to the issue of a construction certificate demonstrating that access is provided to the water and gas meters but they are not to be visually apparent from the street.

(Reason: To protect the appearance of the streetscape)

ADDED: DA2018/001/02 3 September 2020

70. WORKS WITHIN THE ROAD RESERVE (CC)

Detailed drawings including long and short sections and specifications of all works within existing roads (including but not limited to structures, road works, driveway crossings, footpaths and stormwater drainage) shall be submitted to and approved by Council under Section 138 of the Roads Act 1993 and all fees and charges paid, prior to the issue of a Construction Certificate.

Detailed drawings and specifications are to be prepared and certified by an appropriately qualified Civil Engineer.

Pruning of the branches and roots of Council trees is prohibited unless approved by Council in writing.

All Council trees are to be protected in accordance with Australian Standard AS4970 - 2009 , Protection of Trees on Development Sites.

Upon completion of the works, the Applicant is to provide to Council with electronic copies of 'Work as Executed Plans'. The plans are to show relevant dimensions and finished levels and are to be certified by a surveyor.

The Applicant is to provide to Council, in an approved format, details of all public infrastructure created as part of the works.

All civil engineering works adjacent/near/outside 32 Courallie Avenue are to be fully supervised by Council. A maintenance period of six (6) months shall apply to the work, after it has been completed and approved. In that period the Applicant shall be liable for any part of the work which fails to perform in the manner outlined in Council's specifications, or as would reasonably be expected under the design conditions.

(Reason: To ensure compliance of engineering works/Council assets are constructed to acceptable standards for engineering works.)

71. WORKS ZONE - APPROVAL BY COUNCIL'S TRAFFIC COMMITTEE (CC)

An application for a 'Works Zone' must be submitted to and approved by the Strathfield Council Traffic Committee prior to the commencement of any site work (including demolition).

The suitability of the proposed length and duration of the Works Zone is to be demonstrated in the application for the Works Zone. The application for the Works Zone must be submitted to Council at least six (6) weeks prior to the commencement of work on the site to allow for assessment and tabling of agenda for the Strathfield Council Traffic Committee.

The requirement for a Works Zone may be varied or waived only if it can be demonstrated in the Construction Traffic Management Plan (to the satisfaction of Council) that all construction related activities (including all loading and unloading operations) can and will be undertaken wholly within the site. The written approval of Council must be obtained to provide a Works Zone or to waive the requirement to provide a Works Zone prior to the commencement of any site work.

(Reason: Council requirement.)

72. PREVENTION OF NUSIANCE (CC)

All possible and practical steps shall be taken to prevent nuisance to the inhabitants of the surrounding neighbourhood from windblown dust, debris, noise and the like during the demolition, excavation and building works.

(Reason: Health and amenity.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (CW)**73. APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)**

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:
 - notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
 - appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the person having the benefit of the development consent has

given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

74. **DELETED: DA2018/001/02 3 September 2020**

75. **NOTICE OF COMMENCEMENT (CW)**

No work shall commence until the following details are submitted to Council:

- i) a Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- ii) details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- iii) details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DW)

76. **FILL MATERIAL (DW)**

The only waste derived material which may be received at the development site is:

- i) Virgin excavated material (within the meaning of the Protection of the Environment Operations Act 1997), and
- ii) any other waste-derived material the subject of a resource recovery exemption under cl.51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any (b)-type material received at the development site must be accompanied by documentation certifying by an appropriately qualified environmental consultant the materials compliance with the exemption conditions; and this documentation must be provided to the Principal Certifying Authority on request.

(Reason: To ensure imported fill is of an acceptable standard for environmental protection purposes.)

77. **OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)**

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

78. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

79. SURVEY REPORT OF APPROVED LEVELS DURING AND POST CONSTRUCTION (DW)

A Survey Certificate to Australian Height Datum shall be prepared by a Registered Surveyor as follows:

- i) At the completion of the first structural floor level prior to the pouring of concrete indicating the level of that floor and the relationship of the building to the boundaries.
- ii) At the completed height of the building, prior to the placement of concrete form work, or the laying of roofing materials.
- iii) At the completion of the development.

Progress certificates in response to points (1) through to (3) shall be provided to the Principal Certifying Authority at the time of carrying out relevant progress inspections. Under no circumstances is work allowed to proceed until such survey information is submitted to and approved by the Principal Certifying Authority.

(Reason: To ensure compliance with the approved plans.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (OC)

80. CAR PARKING - SURPLUS VEHICULAR CROSSINGS (OC)

All surplus vehicular crossings and/or kerb laybacks must be removed and reinstated with concrete kerb and gutter or to the existing edging profile as specified by Council. The nature strip is to be restored and the footpath area reinstated. All of the above are to be restored to the satisfaction of Council's Engineer and at full cost to the applicant, prior to the issue of any Occupation Certificate.

(Reason: Maintenance of public infrastructure.)

81. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by a suitably Qualified Engineer, with Corporate Membership standing in the Institution of Engineers Australia and registered on the National Professional Engineers Register (NPER) under the appropriate professional category, demonstrating that:

- i) the stormwater drainage system; and/or
- ii) the car parking arrangement and area; and/or
- iii) any related footpath crossing works; and/or
- iv) the proposed basement pump and well system; and/or
- v) the proposed driveway and layback; and/or

- vi) any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

82. FIRE SAFETY CERTIFICATION (OC)

A fire safety certificate shall be obtained in accordance with Part 9, Division 4 of the Environmental Planning and Assessment Regulation 2000, prior to the issue of any Occupation Certificate.

A fire safety certificate is a certificate issued by the owner of a building to the effect that each essential fire safety measure specified in the current fire safety schedule for the part of the building to which the certificate relates:

- i) Has been assessed by a properly qualified person; and
- ii) Was found, when it was assessed, to be capable of performing to at least the standard required by the current fire safety schedule for the building for which the certificate is issued.

An interim fire safety certificate must be provided before an interim occupation certificate can be used for a building under Clause 153(2) of the Environmental Planning & Assessment Regulation 2000.

A final fire safety certificate must be provided before an interim occupation certificate can be used for a building under Clause 153(1) of the Environmental Planning & Assessment Regulation 2000.

A copy of the fire safety certificate and fire safety schedule shall be:

- i) Submitted to Strathfield Council;
- ii) Submitted to the Commissioner of the New South Wales Fire Brigade; and
- iii) Prominently displayed in the building.

(Reason: Fire safety and statutory requirement.)

83. LANDSCAPING - ARBORIST'S FOLLOW UP REPORT OF TREE/S TO BE RETAINED (OC)

As part of the on-going assessment of the tree/s to be retained, the consulting arborist engaged by the applicant is to assess their health and any impacts suffered by them as a result of the proposed approved development, prior to the issue of an Occupation Certificate. Findings are to be compiled in a detailed report and submitted to the Principle Certifying Authority, which documents the following:

- i) Methods of excavation or construction used to carry out the works;
- ii) Any damage sustained by the tree/s as a result of the works;

- iii) Any subsequent remedial works required to be carried out by the consulting arborist as a result of the damage; and
- iv) Any future or on-going remedial work required to be carried out to ensure the long term retention of the tree/s.

(Reason: To ensure the survival of trees to be retained.)

84. **OCCUPATION OF BUILDING (OC)**

A person must not commence occupation or use (or change of use where an existing building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) all required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) any preconditions to the issue of the certificate required by a development consent have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

85. **RAINWATER TANKS (OC)**

Rainwater tanks must be installed on residential properties by a suitably qualified and licensed plumber and in accordance with the following:

- i) Australian/New Zealand Standard AS/NZS 3500:2003;
- ii) NSW Code of Practice Plumbing and Drainage, 2006 produced by Committee on Uniformity of Plumbing and Drainage Regulations in NSW (CUPDR); and
- iii) Council's rainwater tank policy.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To protect public health and amenity.)

86. **STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)**

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

87. **STORMWATER - COVENANT AND RESTRICTION AS TO USER FOR STORMWATER CONTROLLED SYSTEMS (OC)**

Prior to the issue of any Occupation Certificate, the applicant shall register a Positive Covenant and a Restriction as to User under section 88E and or section 88B of the Conveyancing Act as appropriate in favour of Council, ensuring the ongoing retention, maintenance and operation of the stormwater facility (on-site detention, pump-out, charged lines, etc).

Where any drainage line or service conduit is to traverse any property other than that which it serves, an appropriate easement will be required. In this case, the applicant shall register an easement no less than 1200mm wide over the proposed drainage line or service concurrently with any subdivision registration.

The wording on the 88E and/or the 88B Instrument is to make reference to the Council file where the Construction plans and the Work As Executed (as built), plans are held. Typical wording can be obtained from Council's Specification for the Management of Stormwater document.

(Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard.)

88. **ENGINEERING WORKS - CERTIFICATION OF WORK AS EXECUTED (SC)**

Prior to the issue of the Subdivision Certificate, a Work As Executed (WAE) plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by a suitably Qualified Engineer, with Corporate Membership standing in the Institution of Engineers Australia and registered on the National Professional Engineers Register (NPER) under the appropriate professional category, demonstrating that all engineering works including the provision of services, drainage, driveways and earthworks have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council.

(Reason: To ensure adequate access and services have been provided for the new lots.)

CONDITIONS TO BE SATISFIED DURING ONGOING USE OF THE PREMISES (OU)

89. **BOARDING HOUSES - OPERATIONAL PLAN OF MANAGEMENT (OU)**

An Operational Plan of Management is to be formulated and submitted to Council for approval, prior to the issue of any Occupation Certificate.

The Plan of Management must include the minimum criteria as stipulated in Schedule 2 (Standards for Places of Shared Accommodation) of the Local Government (General) Regulation, 2005 under the Local Government Act 1993, the Public Health Act, 1991, Boarding Houses Act 2012 and Boarding Houses Regulation 2013.

The plan shall be dated and the name and signature of the author of the document shall be included. The Plan of Management shall be displayed in prominent locations within the premises and a copy of the Plan shall be provided to all residents of the boarding house. The on-site Caretaker shall be responsible for ensuring that the terms of the Plan are adhered to at all times.

This Operational Plan of Management must incorporate the following:

- i) All the measures to be implemented on the premises in terms of safety & security, amenity and health including but not limited to matters relating to curfews and after-hours access, bringing of visitors on to the site, drug and alcohol policy (including smoking), and use of communal areas etc.
- ii) All the responsibilities of the Caretaker/Manager.
- iii) An Incident Register to be maintained by the Caretaker. This Register must be

produced upon demand by any Council officer or NSW Police Officer. The Register must contain a direction that all incidents of a criminal nature are to be reported to the Police immediately.

- iv) Prior to commencement of the boarding house use, a notification letter shall be forwarded to Council, the Police and neighbours providing contact details for the Caretaker/Manager so that any issues regarding the operation of the premises etc can be addressed promptly. Evidence of this letter being forwarded as required in this condition shall be provided to the Principal Certifying Authority, prior to the issue of any Occupation Certificate and commencement of the use.

The Plan of Management referred to in this condition shall be reviewed by Council annually from the date of issue of an Occupation Certificate by the Principal Certifying Authority. The operator of the boarding house shall contact Council annually to carry out this review and the review shall include the Incident Register referred to in point (iii) above. Should amendments be made to the Plan of Management an updated version of same shall be provided to Council and the residents of the boarding house within one (1) month of the annual review being completed.

(Reason: To minimise the impact of the use on surrounding residences.)

90. **BOARDING HOUSE - ONGOING USE OF (OU)**

Ongoing operation of the approved use for the purpose of a boarding house shall comply with the following:

- i) Use of the premises shall remain consistent with the definition of 'boarding house' as defined under Strathfield Local Environmental Plan 2012 as a building that:
- is wholly or partly let in lodgings, and
 - provides lodgers with a principal place of residence for 3 months or more, and
 - may have shared facilities, such as a communal living room, bathroom, kitchen or laundry, and
 - has rooms, some or all of which may have private kitchen and bathroom facilities, that accommodate one or more lodgers but does not include backpackers" accommodation, a group home, a serviced apartment, seniors housing or hotel or motel accommodation.
- ii) Subdivision of the approved boarding house under strata or community title is prohibited.
- iii) The use and operation of the boarding house shall comply with all applicable legislation/regulation and standards, including:
- Boarding Houses Act 2012;
 - Boarding Houses Regulation 2013;
 - Local Government Act 1993; and
 - Schedule 2 (Standards for Places of Shared Accommodation) of the Local Government (General) Regulation 2005.
- iv) The maximum number of persons accommodated in a bedroom, or in a cubicle of a dormitory, must not exceed the number determined by allowing a minimum floor area within the bedroom or cubicle in accordance with the relevant provisions under the Public Health Act 1991 for each person.
- v) No speakers or music is permitted outdoors or in the communal areas.
- vi) The Boarding house is required to be registered on a register administered by NSW Fair Trading.

(Reason: To minimise the impact of the boarding house on surrounding residences.)

91. WASTE AND RECYCLING COLLECTION (COMMERCIAL AND INDUSTRIAL) (OU)**i) DELETED**

- ii) Commercial and industrial garbage and recycling must be collected on site unless expressly agreed to in OC.
- iii) Where consent is given for commercial and industrial garbage and recycling to be placed kerbside for collection bins must not be placed on the kerbside more than one hour before the scheduled collection time. Bins and containers are to be removed from the kerbside within one (1) hour of collection and returned to the designated garbage storage area(s).
- iv) The garbage and recyclable storage area and bins must be adequate to contain the volume and type of garbage and recyclable matter of the food premises.
- v) All garbage and recyclable matter must be enclosed in the waste bins with lids completely closed at all times.
- vi) Recycling options must be provided for all commercially recyclable waste products including but not limited to paper, cardboard, oil, food waste, plastics, metals, chemicals etc.
- vii) The waste collection is to occur outside the peak hours as approved by Council's Waste Management Officer of the operation of the car park to minimise the conflicts with other traffic movements from/into the site.**

(Reason: To regulate noise and garbage collection arrangements.)

MODIFIED: DA2018/001/02 3 September 2020

92. FIRE SAFETY ANNUAL STATEMENT (OU)

Pursuant to Part 9, Division 5 of the Environmental Planning and Assessment Regulation (as amended) the owner of the building shall provide to Council an Annual Fire Safety Statement from an appropriately qualified person certifying the essential fire safety measures in the building. The Annual Fire Safety Statement shall be submitted within 12 months of the issue of the fire safety certificate, and then on an annual basis.

A copy of the Fire Safety Statement obtained and Fire Safety Schedule shall also be:

- i) Forwarded to the Commissioner of the New South Wales Fire Brigade; and
- ii) Prominently displayed in the building.

(Reason: Fire safety.)

93. PLANT NOISE FROM PREMISES (OU)

Noise emissions from plant and equipment operating on the site, including air conditioners, shall be minimised by installing and regularly maintaining attenuation. Attenuation measures shall be tested to ensure noise from the air conditioners is not audible at the nearest residential receiver after 10pm and the results of that testing provided to Council.

(Reason: To minimise the noise disturbance during operation of the premises)

94. NOISE FROM COMMON ROOF

The common rooftop area shall not be used after 9pm and the Plan of Management shall amended to reflect this.

(Reason: To minimise the noise disturbance during operation of the premises.)

95. PLAN OF MANAGEMENT MUST BE DEVELOPED AND APPROVED BY COUNCIL (OC)

Plan of Management to include:

1. How the building manager will present and maintain waste bins to minimise collection time.
2. How and when the building manager will present bins for safe and efficient collection (collection day is Thursday).
3. How and when the building manager will dispose of any bulky waste stored either in the designated bulky waste storage area or anywhere on site (must be within 48 hours).
4. How and when the building manager will clean bins and the waste storage room.
5. What kind of access the residents will have to the bin storage room/ if the rooms will have 2 small bins which are serviced by the building manager every 2 days.
6. Provision for hand compaction including the provision of a hand compactor.

(Reason: To ensure waste is collected)

96. CONTROL OF LITTER (OU)

The occupant or person in control of the premises must take all practicable steps to ensure that the area of public footpath or public area adjacent to the premises is maintained in a clean and tidy condition.

A litter management plan must be included with all applications, litter management plan must include the below:

- i) All steps being taken to prevent, reduce and collect any litter produced by the site
- ii) Measures such as cleaner to conduct litter collection within a 50m radius to be included.

(Reason: To manage litter throughout the LGA.)

97. DELETED: DA2018/001/02 3 September 2020**RESOLUTION**

This modification application is **APPROVED** subject to the recommended conditions of consent within the report as amended by the Panel.

FOR: Paul Stein, Eric Armstrong, David Starr, Jan Murrell

AGAINST: Nil

Reason: The Panel concurs with the Planning Officers report.

**** End Minutes - Report No. 32****

TO: Strathfield Local Planning Panel Meeting - 3 September 2020
REPORT: SLPP – Report No. 33
SUBJECT: DA2020/112: 56 CHURCHILL AVENUE, STRATHFIELD
 LOT 1 DP 913096
DA NO. 2020/112

RECOMMENDATION

That Development Application No. 2020/112 for alterations and additions to an existing dwelling including new two storey rear extension and tandem carport at 56 Churchill Avenue, Strathfield be **APPROVED**, subject to the following conditions:

The following conditions of consent are imposed for the following reasons:

- (a) To ensure compliance with the terms of the relevant Environmental Planning Instrument and/or Building Code of Australia and/or Council's codes, policies and specifications.
- (b) To protect the environment.
- (c) To ensure that there is no unacceptable impact on the amenity of the area, or to private and public property.
- (d) It is in the public interest.

1. Approved Plans & Documentation

The development must be implemented in accordance with the approved plans and supporting documentation listed below which have been endorsed by Council's approved stamp, except where marked up on the plans and/or amended by conditions of this consent:

Description	Reference No.	Date	Revision	Prepared by
Ground Floor Plan / Demolition Plan	DA03	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
Ground Floor Plan	DA04	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
Ground Floor Plan	DA05	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
First Floor Plan	DA06	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
Roof Plan	DA07	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
North and South Elevation Plan	DA08	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
East and West Elevation Plan	DA09	2 June 2020	A	Studio Make Made – received by Council 19 June 2020
Section A and Section B Plan	DA10	2 June 2020	A	Studio Make Made – received by Council 19 June 2020

Stormwater Plans	A20102	4 June 2020	A	Alpha Engineering - received by Council 19 June 2020
Waste Management Plan	-	20 June 2017	A	Vivien Van Phung – received by Council 19 June 2020
Landscape Plans	L/01, L/02, L/03	4 June 2020	A	Aspect Designs – 19 June 2020
Arborist Report		15 June 2020		The Tree MD – received by Council 19 June 2020
Arboriculture Root Mapping		6 August 2020		The Tree MD – received by Council 7 August 2020
Flood Impact Statement		27 May 2020	A	Studio Make Made – received by Council 19 June 2020

2. Building Height

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) 18.50m AHD to the roof ridge of the new rear additions of the dwelling.

SEPRARATE APPROVALS REQUIRED UNDER OTHER LEGISLATION

3. Section 138 Roads Act 1993 and Section 68 Local Government Act 1993

Unless otherwise specified by a condition of this consent, this Development Consent does not give any approval to undertake works on public infrastructure.

Separate approval is required under Section 138 of the [Roads Act 1993](#) and/or Section 68 of the [Local Government Act 1993](#) for any of the following activities carried out in, on or over a public road (including the footpath) listed below.

An application is required to be lodged and approved prior to the commencement of any of the following works or activities;

- (a) Placing or storing materials or equipment;
- (b) Placing or storing waste containers or skip bins;
- (c) Erecting a structure or carrying out work
- (d) Swinging or hoisting goods over any part of a public road by means of a lift, crane or the like;
- (e) Pumping concrete from a public road;
- (f) Pumping water from the site into the public road;
- (g) Constructing a vehicular crossing or footpath;
- (h) Establishing a “works zone”;
- (i) Digging up or disturbing the surface of a public road (e.g. Opening the road for the

purpose of connections to utility providers);

- (j) Stormwater & ancillary works in the road reserve; and
- (k) Stormwater & ancillary to public infrastructure on private land
- (l) If any excavation is to be supported by the use of below ground (cable) anchors that are constructed under Council's roadways/footways.

These separate activity approvals must be obtained and evidence of the approval provided to the Certifying Authority prior to the issue of the Construction Certificate.

The relevant Application Forms for these activities can be downloaded from Council's website www.strathfield.nsw.gov.au. For further information, please contact Council's Customer Service Centre on (02) 9748 9999.

REQUIREMENTS OF CONCURRENCE, INTEGRATED & OTHER GOVERNMENT AUTHORITIES

4. Sydney Water – Tap in™

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see 'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

5. Required Design Changes

The following changes are required to be made and shown on the Construction Certificate plans:

Rear alfresco Height	The maximum height of the rear alfresco area must be reduced from the proposed RL 11.85 to RL 11.60 or below.
Reduction of rear balcony depth	The rear balcony adjoining the master bedroom must be reduced in size to achieve a depth no greater than 1m.

6. Fees to be Paid

The fees listed in the table below must be paid in accordance with the conditions of this consent and Council's adopted Fees and Charges applicable at the time of payment (available at www.strathfield.nsw.gov.au).

Payments must be made prior to the issue of the Construction Certificate or prior to the commencement of work (if there is no associated Construction Certificate).

Please contact council prior to the payment of s7.11 or s7.12 Contributions to determine whether the amounts have been indexed from that indicated below in this consent and the form of payment that will be accepted by Council.

A summary of the fees to be paid are listed below:

Fee Type	Fee
GENERAL FEES	
Long Service Levy (to Long Service Corporation)	\$ 1,750.00
Or, provide evidence of Payment direct to the Long Service Corporation. See https://portal.longservice.nsw.gov.au/bci/levy/	
Security Damage Deposit	\$ 12,200.00
Tree Bond	\$ 3,000.00
Administration Fee for Damage Deposit	\$ 127.00
Administration Fee for tree bond	\$127.00

DEVELOPMENT CONTRIBUTIONS

Strathfield Section 94A Indirect Development Contributions Plan 2017	\$ 5,000.00
--	--------------------

General Fees

The fees and charges above are subject to change and are as set out in the version of Council's Schedule of Fees and Charges or as required by other Government Authorities, applicable at the time of payment.

Development Contributions

The Section 7.11 contribution (s94) is imposed to ensure that the development makes adequate provision for the demand it generates for public amenities and public services within the area.

A Section 7.12 contribution has been levied on the subject development pursuant to the Strathfield Section 94A Indirect Development Contributions Plan.

Indexation

The above contributions will be adjusted at the time of payment to reflect changes in the cost of delivering public amenities and public services, in accordance with the indices provided by the relevant Development Contributions Plan.

Timing of Payment

The contribution must be paid and receipted by Council:

- Prior to the consent being acted upon.

Further Information

A copy of the *current Development Contributions Plans* may be inspected at Council's Customer Service Centre at 65 Homebush Road, Strathfield or on Council's website www.strathfield.nsw.gov.au.

7. **Schedule of External Colours and Finishes**

a) Existing House

The external colour scheme and material finishes are to comprise predominantly of colours and materials that have a hue and tonal relationship that is in keeping with the overall Federation character of the building and/or character of the Heritage Conservation Area. A schedule confirming all external materials, colours and finishes including windows, doors and roofing materials shall be submitted to and approved by Council's Heritage Advisor prior to the issue of the Construction Certificate. The documentation must show the distribution of the colours on the elevation drawings, specify paint types and include colour swatches/colour names and codes.

It is recommended that reference be made to the book "Colour Schemes for Old Australian Houses" by Ian Evans, Clive Lucas and Ian Stapleton.

b) Proposed Extension

An external colour and material scheme is to comprise predominantly of colours and materials that have a hue and tonal relationship that is in keeping with the overall Federation character of the building and the character of the Heritage Conservation Area. This shall include the carport structure.

The façade of the new extension needs to be of a material such as brick of a recessive hue and the roof of terra cotta Marseilles tiles that is in keeping with the Federation era of the house. A schedule confirming all external materials, colours and finishes including windows, doors and roofing materials shall be submitted to and approved by Council's Heritage Advisor prior to the issue of the Construction Certificate. The documentation must show the distribution of the colours on the elevation drawings, specify paint types and include colour swatches/colour names and codes.

8. **Damage Deposit – Minor Works**

In order to insure against damage to Council property the following is required:

- (a) Pay Council, before the issue of the Construction Certificate, a damage security deposit for the cost of making good any damage caused to any Council property as a result of the development: **\$12,200**.
- (b) Pay Council, before the issue of the Construction Certificate, a non-refundable administration fee to enable assessment of any damage and repairs where required: **\$254.00** (inclusive of tree bond administration fee)
- (c) Submit to Council, before the commencement of work, a photographic record of the condition of the Council nature strip, footpath and driveway crossing, or any area likely to be affected by the proposal.

At the completion of work Council will inspect the public works, and the damage deposit will be refunded in full upon completion of work where no damage occurs. Otherwise the

amount will be either forfeited or partly refunded according to the amount of damage.

9. **Tree Bond**

A tree bond of **\$3,000** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A request for refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

10. **Site Management Plan**

Minor Development

A Site Management Plan detailing all weather access control points, sedimentation controls, waste management plans, fencing, builder's site sheds office, amenities, materials storage and unloading arrangements must be submitted with the application for the Construction Certificate.

The site management measures are to be implemented prior to the commencement of any works including demolition and excavation. The site management measures are to be maintained throughout the works, to maintain reasonable levels of public health, safety and amenity. A copy of the Site Management Plan must be kept on site and is to be made available upon request.

11. **BASIX Commitments**

The approved BASIX Certificate shall be submitted to the Accredited Certifier with the application for a Construction Certificate.

All measures and commitments as detailed in the BASIX Certificate No. A377428 must be implemented on the plans lodged with the application for the Construction Certificate.

12. **Front Fence in Conservation Areas and Heritage Items**

The front fence and gates must be in the traditional federation period fence form. The total height of the fence measured from natural ground is to be no more than 1200mm. Details are to be submitted and approved by Council's Heritage Advisor prior to the issue of the Construction Certificate.

13. **Retain/restore front footpath**

The existing footpath must be retained in concrete in its current design. This footpath is a landscape element that is consistent within the streetscape.

14. Erosion & Sedimentation Control

Erosion and sediment controls must be provided to ensure:

- (a) Compliance with the approved Erosion & Sediment Control Plan
- (b) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval)
- (c) All clean water run-off is diverted around cleared or exposed areas
- (d) Silt fences, stabilised entry/exit points or other devices are installed to prevent sediment from entering drainage systems or waterways
- (e) All erosion and sediment controls are fully maintained for the duration of demolition, excavation and/or development works
- (f) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadway
- (g) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar
- (h) Compliance with [Managing Urban Stormwater – Soils and Construction \(Blue Book\) produced by Landcom 2004.](#)

These measures are to be implemented prior to the commencement of work (including demolition and excavation) and must remain until works are completed and all exposed surfaces are landscaped/sealed.

15. Stormwater System

The submitted stormwater plan has been assessed as a concept plan only. Final detailed plans of the drainage system in accordance with Council stormwater management code and AS/NZS 3500.3: 2015 (as amended), prepared by a professional engineer specialising in hydraulic engineering, shall be submitted for approval with the Construction Certificate.

16. Detailed Stormwater Drainage Design

The submitted stormwater plan has been assessed as a concept plan only. A detailed drainage design supported by a catchment area plan and drainage calculations (including a Hydraulic Grade Line Analysis) in accordance with Council's Stormwater Management Code must be submitted with the Construction Certificate application.

17. Compliance with Flood Study

The development shall be designed to conform to the recommendations and conclusions of the submitted flood impact statement prepared by ALPHA Engineering and Development rev A dated 27.05.2020.

This shall include, but not be limited to, any recommendations for the following:

- (a) Minimum floor levels
- (b) Fencing

- (c) Site regrading
- (d) Overland flow path construction
- (e) Protection of the basement from inundation of surface waters

Evidence from professional engineer that specialises in hydraulic engineering that all design requirements have been adhered to shall be submitted with the Construction Certificate application.

18. Drainage System – Maintenance of Existing System

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

19. Engineer's Certificate

A certificate from a professional Engineer specialising in structural engineering certifying the structural adequacy of the existing structure, to support all proposed additional superimposed loads shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

20. Tree Removal/Pruning Prohibited

This consent does not approve the removal or pruning (branches or roots) of any trees on the subject property, Council's public footway, public reserves or on neighbouring properties.

21. Compliance with Submitted Arborist Report

The recommendations outlined in the Arborist's Report titled The Tree Root Mapping report by The Tree MD, dated 6 August 2020 must be implemented throughout the relevant stages of construction. The following amendments must be made to the tree protection plan:

1. The incursion into the TPZ is calculated as being 9.9%. Appendix D Encroachment into tree protection zone (page 29) of AS4970-2009, requires an equal area as compensation for all TPZ encroachment. Prior to the CC the applicant is to provide an amended tree protection plan (annexures 9 & 11) to demonstrate how the protected trees will be managed in acknowledgement of this requirement for an adjusted TPZ.

The following amendments must be made to the stormwater plan:

2. The stormwater plan is to be amended prior to the Construction certificate to comply with 4.5.5 of AS 4970-2009 or are to be suspended under rear deck/veranda, supported by saddles. An AQF level 5 consultant arborist is to sign off on this amendment in order to protect the adjacent trees.

Details of tree protection measures to be implemented must be detailed and lodged with

the Construction Certificate application for approval and shall be in accordance with Section 4 - Australian Standard AS 4970-2009: Protection of trees on development sites.

The tree/s to be protected are listed in the table below.

Tree No.	Tree Species	Location of Tree	Tree Protection Zone (metres)
1	Silky Oak	Rear yard	7.69
2	Red Gum Eucalyptus	Rear yard	15
3	Jacaranda	Rear yard	4.68
4	Lemon Scented Gum	Adjoining property	7.20
5	Brush Box	Council Verge	6.12
6	Brush Box	Council Verge of adjoining property	5.28

PRIOR TO THE COMMENCEMENT OF WORK (INCLUDING DEMOLITION & EXCAVATION)

22. Demolition & Asbestos

The demolition work shall comply with the provisions of Australian Standard AS2601:2001 – Demolition of Structures, NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#). The work plans required by AS2601:2001 shall be accompanied by a written statement by a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the safety statement shall be submitted to the PCA prior to the commencement of works.

For demolition work which involves the removal of asbestos, the asbestos removal work must be carried out by a licensed asbestos removalist who is licensed to carry out the work in accordance with the NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#) unless specified in the Act and/or Regulation that a license is not required.

All demolition work including the removal of asbestos, shall be undertaken in accordance with the [Demolition Code of Practice](#) (NSW Work Cover July 2015)

Note: Copies of the Act, Regulation and Code of Practice can be downloaded free of charge from the SafeWork NSW website: www.SafeWork.nsw.gov.au.

23. Demolition Notification Requirements

The following notification requirements apply to this consent:

- (a) The developer /builder must notify adjoining residents five (5) working days prior to demolition. Such notification is to be a clearly written note giving the date demolition will commence, contact details of the developer/builder, licensed asbestos demolisher and the appropriate regulatory authority. Notification is to be placed in the letterbox of

every premises (including every residential flat or unit, if any) either side and immediately at the rear of the demolition site.

- (b) Five (5) working days prior to demolition, the developer/builder is to provide written notification to Council advising of the demolition date, details of the SafeWork licensed asbestos demolisher and the list of residents advised of the demolition.
- (c) On demolition sites where buildings to be demolished contain asbestos, a standard commercially manufactured sign containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm is to be erected in a prominent visible position (from street frontage) on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos material has been removed from the site to an approved waste facility.

24. Demolition Work Involving Asbestos Removal

Work involving bonded asbestos removal work (of an area of more than 10 square metres) or friable asbestos removal work must be undertaken by a person who carries on a business of such removal work in accordance with a licence under clause 458 of the [Work Health and Safety Regulation 2011](#).

25. Dial Before You Dig

The applicant shall contact "Dial Before You Dig on 1100" to obtain a Service Diagram prior to the issuing of the Construction Certificate. The sequence number obtained from "Dial Before You Dig" shall be forwarded to Council's Engineers for their records.

26. Registered Surveyors Report - During Development Work

A report must be submitted to the PCA at each of the following applicable stages of construction:

- (a) Set out before commencing excavation.
- (b) Floor slabs or foundation wall, before formwork or commencing brickwork.
- (c) Completion of Foundation Walls - Before any construction of flooring, detailing the location of the structure relative to adjacent boundaries and floor levels relative to the datum shown on the approved plans.
- (d) Completion of Floor Slab Formwork - Before pouring of concrete/walls construction, detailing the location of the structure relative to adjacent boundaries and floor levels relative to the datum shown on the approved plans. In multi-storey buildings a further survey must be provided at each subsequent storey.
- (e) Completion of any Pool Formwork - Before concreting of pool shell, detailing the location of the pool relative to the adjacent boundaries and its height relative to the datum shown on the approved plans.
- (f) Completion of any Roof Framing - Before roof covered detailing eaves/gutter setback from boundaries.
- (g) Completion of all Work - Detailing the location of the structure (including eaves/gutters) relative to adjacent boundaries and its height relative to the datum shown on the approved plans. A final Check Survey must indicate the reduced level of the main ridge.

Work must not proceed beyond each stage until the PCA is satisfied that the height and location of the building is proceeding in accordance with the approved plans.

DURING CONSTRUCTION**27. Site Sign – Soil & Erosion Control Measures**

Prior to the commencement of works (including demolition and excavation), a durable site sign, issued by Council in conjunction with this consent, must be erected in a prominent location on site. The site sign warns of the penalties which apply to pollution, storing materials on road or footpath and breaches of the conditions relating to erosion and sediment controls. The sign must remain in a prominent location on site up until the completion of all site and building works.

28. Hours of Construction for Demolition and Building Work

Any work activity or activity associated with the development consent that requires the use of any tools (including hand tools) or any power operated plant and machinery that creates noise on or adjacent to the site shall not be performed, or permitted to be performed, except between the hours of 7.00 am to 5.00 pm, Monday to Friday and 8:00am to 1:00pm on Saturdays. No work or ancillary activity is permitted on Sundays, or Public Holidays.

Where the development involves the use of jack hammers/rock breakers and the like, or other heavy machinery, such equipment may only be used between the hours of 7:00am to 5:00pm Monday to Friday only.

Note: A penalty infringement notice may be issued for any offence.

29. Ground Levels and Retaining Walls

The ground levels of the site shall not be excavated, raised or filled, or retaining walls constructed on the allotment boundary, except where indicated on approved plans or approved by Council.

30. Obstruction of Road or Footpath

The use of the road or footpath for the storage of any building materials, waste materials, temporary toilets, waste or skip bins, or any other matter is not permitted unless separately approved by Council under Section 138 of the [Roads Act 1993](#) and/or under Section 68 of the [Local Government Act 1993](#). Penalty infringement Notices may be issued for any offences and severe penalties apply.

31. Construction Management Plan

The owner/applicant is to ensure that the approved Construction Traffic management Plan is to be strictly complied with and kept on site at all times during construction works.

PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE**32. BASIX Certificate**

All energy efficiency measures as detailed in the approved BASIX Certificate in the plans approved with the Development Consent, must be implemented before issue of any Occupation Certificate.

33. BASIX Compliance Certificate

A Compliance Certificate must be provided to the PCA regarding the implementation of all energy efficiency measures as detailed in the approved BASIX Certificate before any

Occupation Certificate is issued.

34. **Completion of Landscape Works**

At the completion of all works, a certificate is to be submitted to the Principal Certifying Authority from a qualified Landscape and/or Arboricultural Consultant certifying that the work has been completed in accordance with the approved Landscape Plan and that a maintenance program has been established.

35. **Flood Prone Land – Survey of Levels**

A registered surveyor shall verify the levels of the design runoff overland flow path and finished floor levels to Australian Height Datum. The surveyor is also to verify that the flow paths and finished floor levels have been built to the design levels, dimensions and surface finishes as specified in the approved plans.

36. **Stormwater Certification of the Constructed Drainage Works (Minor)**

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

OPERATIONAL REQUIREMENTS UNDER THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979

37. **Requirement for a Construction Certificate**

The erection of a building must not commence until a Construction Certificate has been issued.

38. **Appointment of a PCA**

The erection of a building must not commence until the applicant has:

- (a) Appointed a PCA for the building work; and
- (b) If relevant, advised the PCA that the work will be undertaken as an Owner -Builder.

If the work is not going to be undertaken by an Owner - Builder, the applicant must:

- (c) Appoint a Principal Contractor to undertake the building work. If residential building work (within the meaning of the [Home Building Act 1989](#)) is to be undertaken, the Principal Contractor must be a holder of a contractor licence; and
- (d) Notify the PCA of the details of any such appointment; and
- (e) Notify the Principal Contractor of any critical stage inspections or other inspections that are required to be carried out in respect of the building work.

39. **Notification of Critical Stage Inspections**

No later than two days before the building work commences, the PCA must notify:

- (a) The consent authority and the Council (if not the consent authority) of his or her appointment; and

- (b) The applicant of the critical stage inspections and other inspections that are to be carried out with respect to the building work.

40. **Notice of Commencement**

The applicant must give at least two days notice to the Council and the PCA of their intention to commence the erection of a building.

41. **Critical Stage Inspections**

The last critical stage inspection must be undertaken by the PCA. The critical stage inspections required to be carried out vary according to Building Class under the Building Code of Australia and are listed in Clause 162A of the [Environmental Planning and Assessment Regulation 2000](#).

42. **Notice to be Given Prior to Critical Stage Inspections**

The principal contractor for a building site, or the owner-builder, must notify the PCA at least 48 hours before each required inspection needs to be carried out.

43. **Occupation Certificate**

A person must not commence occupation or use of the whole or any part of a new building unless an Occupation Certificate has been issued in relation to the building or part.

PRESCRIBED CONDITIONS

44. **Clause 97A – BASIX Commitments**

This Clause requires the fulfilment of all BASIX Commitments as detailed in the BASIX Certificate to which the development relates.

45. **Clause 98 – Building Code of Australia & Home Building Act 1989**

Requires all building work to be carried out in accordance with the Building Code of Australia. In the case of residential building work to which the [Home Building Act 1989](#) relates, there is a requirement for a contract of insurance to be in force before any work commences.

46. **Clause 98A – Erection of Signs**

Requires the erection of signs on site and outlines the details which are to be included on the sign. The sign must be displayed in a prominent position on site and include the name and contact details of the PCA and the Principal Contractor.

RESOLUTION

The Development Application be **APPROVED** subject to the recommended conditions of consent in the report.

FOR: Paul Stein, Eric Armstrong, David Starr, Jan Murrell

AGAINST: Nil

Reasons: The Panel concurs with the Planning Officers report.

**** End Minutes - Report No. 33****

TO: Strathfield Local Planning Panel Meeting - 3 September 2020
REPORT: SLPP – Report No. 34
SUBJECT: DA2020/081: 74-76 HOMEBUSH ROAD, STRATHFIELD
 LOT 2 DP4508
DA NO. 2020/081

RECOMMENDATION

That Development Application No. 2020/118 for adaptive reuse of existing dwelling to an educational establishment containing a playground, ancillary landscaping and fencing at 74-76 Homebush Road, Strathfield be **APPROVED**, subject to the following conditions:

The following conditions of consent are imposed for the following reasons:

- (a) To ensure compliance with the terms of the relevant Environmental Planning Instrument and/or Building Code of Australia and/or Council's codes, policies and specifications.
- (b) To protect the environment.
- (c) To ensure that there is no unacceptable impact on the amenity of the area, or to private and public property.
- (d) It is in the public interest.

DEVELOPMENT DETAILS

1. Approved Plans & Documentation

The development must be implemented in accordance with the approved plans and supporting documentation listed below which have been endorsed by Council's approved stamp, except where marked up on the plans and/or amended by conditions of this consent:

Description	Reference No.	Date	Revision	Prepared by
Site Plan	DA01	14 April 2020	A	Morson group – received by Council 4 May 2020
Demolition Plan	DA02	14 April 2020	A	Morson group – received by Council 4 May 2020
Proposed Floor / Landscape Plan	DA05	1 June 2020	B	Morson group – received by Council 22 June 2020
Fencing Detail Plans	DA06	14 April 2020	A	Morson group – received by Council 4 May 2020
Landscape Plan	Sheet 1 of 2	11 June 2020	A	Paul Scrivener – received by Council 22 June 2020

MINUTES

Landscape Plan	Sheet 2 of 2	11 June 2020	A	Paul Scrivener – received by Council 22 June 2020
Stormwater Plan – Cover Sheet	D00	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Stormwater Drainage Plan	D01	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Stormwater Easement Layout Plan	D03	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Stormwater Pre and post Development Catchment Plan	D05	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Stormwater Drainage Sections and Details Plan	D06	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Stormwater drainage Design Calculations	D07	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Erosion and Sediment Control Plan and Details	D10	June 2020	A	Smart Structures Australia – received by Council 23 June 2020
Acoustic Report	-	2 June 2020	0	Rodney Stevens Acoustics – received by Council 27 July 2020
Building Code of Australia Report	-	15 April 2020	1	360 Certification – received by Council 4 May 2020
Waste Management Plan	-	23 April 2020	-	Peter Morson – received by Council 4 May 2020
Access Report	-	-	Ref2002 6	Vista Architects – received by Council 4 May 2020

2. Restrictions on Use

The following restrictions on the hours of use of the premise are placed as follows:

Building	7:30am-5:30pm Monday to Friday inclusive of school holidays, weekends and public holidays
Outdoor Play Area	8am-5:30pm (School days, weekends and public holidays)

The use of the premises shall be limited to school purposes. The use of the first floor and basement area shall be restricted to administrative purposes and storage and not available to the students.

SEPRARATE APPROVALS REQUIRED UNDER OTHER LEGISLATION

3. Section 138 Roads Act 1993 and Section 68 Local Government Act 1993

Unless otherwise specified by a condition of this consent, this Development Consent does not give any approval to undertake works on public infrastructure.

Separate approval is required under Section 138 of the [Roads Act 1993](#) and/or Section 68 of the [Local Government Act 1993](#) for any of the following activities carried out in, on or over a public road (including the footpath) listed below.

An application is required to be lodged and approved prior to the commencement of any of the following works or activities;

- (a) Placing or storing materials or equipment;
- (b) Placing or storing waste containers or skip bins;
- (c) Erecting a structure or carrying out work
- (d) Swinging or hoisting goods over any part of a public road by means of a lift, crane or the like;
- (e) Pumping concrete from a public road;
- (f) Pumping water from the site into the public road;
- (g) Constructing a vehicular crossing or footpath;
- (h) Establishing a "works zone";
- (i) Digging up or disturbing the surface of a public road (e.g. Opening the road for the purpose of connections to utility providers);
- (j) Stormwater & ancillary works in the road reserve; and
- (k) Stormwater & ancillary to public infrastructure on private land
- (l) If any excavation is to be supported by the use of below ground (cable) anchors that are constructed under Council's roadways/footways.

These separate activity approvals must be obtained and evidence of the approval provided to the Certifying Authority prior to the issue of the Construction Certificate.

The relevant Application Forms for these activities can be downloaded from Council’s website www.strathfield.nsw.gov.au. For further information, please contact Council’s Customer Service Centre on (02) 9748 9999.

REQUIREMENTS OF CONCURRENCE, INTEGRATED & OTHER GOVERNMENT AUTHORITIES

4. Sydney Water – Tap in™

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water’s sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to ‘Plumbing, building and developing’ section of Sydney Water’s web site at www.sydneywater.com.au then see ‘Building’, or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

5. Fees to be Paid

The fees listed in the table below must be paid in accordance with the conditions of this consent and Council’s adopted Fees and Charges applicable at the time of payment (available at www.strathfield.nsw.gov.au).

Payments must be made prior to the issue of the Construction Certificate or prior to the commencement of work (if there is no associated Construction Certificate).

Please contact council prior to the payment of s7.11 or s7.12 Contributions to determine whether the amounts have been indexed from that indicated below in this consent and the form of payment that will be accepted by Council.

A summary of the fees to be paid are listed below:

Fee Type	Fee
GENERAL FEES	
Long Service Levy (to Long Service Corporation)	\$700.00
Or, provide evidence of Payment direct to the Long Service Corporation. See https://portal.longservice.nsw.gov.au/bci/levy/	
Security Damage Deposit	\$ 5,200.00
Tree Bond	\$ 20,000.00
Administration Fee for Damage Deposit	\$ 127.00
Administration Fee for Tree Bond	\$127.00

Strathfield Section 94A Indirect Development Contributions Plan 2017 **\$ 2,000.00**

General Fees

The fees and charges above are subject to change and are as set out in the version of Council's Schedule of Fees and Charges or as required by other Government Authorities, applicable at the time of payment.

Development Contributions

The Section 7.11 contribution (s94) is imposed to ensure that the development makes adequate provision for the demand it generates for public amenities and public services within the area.

A Section 7.12 contribution has been levied on the subject development pursuant to the Strathfield Section 94A Indirect Development Contributions Plan.

Indexation

The above contributions will be adjusted at the time of payment to reflect changes in the cost of delivering public amenities and public services, in accordance with the indices provided by the relevant Development Contributions Plan.

Timing of Payment

The contribution must be paid and receipted by Council

- prior to the release of the Construction Certificate.

Further Information

A copy of the *current Development Contributions Plans* may be inspected at Council's Customer Service Centre at 65 Homebush Road, Strathfield or on Council's website www.strathfield.nsw.gov.au.

6. **DELETED**

7. **Damage Deposit – Minor Works**

In order to insure against damage to Council property the following is required:

- (a) Pay Council, before the issue of the Construction Certificate, a damage security deposit for the cost of making good any damage caused to any Council property as a result of the development: **\$5,200**.
- (b) Pay Council, before the issue of the Construction Certificate, a non-refundable administration fee to enable assessment of any damage and repairs where required: **\$127.00**.
- (c) Submit to Council, before the commencement of work, a photographic record of the condition of the Council nature strip, footpath and driveway crossing, or any area likely to be affected by the proposal.

At the completion of work Council will inspect the public works, and the damage deposit will be refunded in full upon completion of work where no damage occurs. Otherwise the

amount will be either forfeited or partly refunded according to the amount of damage.

8. **Tree Bond**

A tree bond of **\$20,000** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A request for refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

9. **Site Management Plan**

Minor Development

A Site Management Plan detailing all weather access control points, sedimentation controls, waste management plans, fencing, builder's site sheds office, amenities, materials storage and unloading arrangements must be submitted with the application for the Construction Certificate.

Major Development

A Site Management Plan must be submitted with the application for a Construction Certificate, and include the following:

- (a) Location of protective site fencing;
- (b) Location of site storage areas/sheds/equipment;
- (c) Location of building materials for construction, e.g. stockpiles
- (d) Provisions for public safety;
- (e) Dust control measures;
- (f) Method used to provide site access location and materials used;
- (g) Details of methods of disposal of demolition materials, according to Waste Management Plan and which should be used or recycled wherever practicable;
- (h) Method used to provide protective measures for tree preservation;
- (i) Provisions for temporary sanitary facilities;
- (j) Location and size of waste containers/skip bins, according to the Waste Management Plan and including resource recovery methods;
- (k) Details of proposed sediment and erosion control measures;
- (l) Method used to provide construction noise and vibration management;
- (m) Construction and demolition traffic management details.

The site management measures are to be implemented prior to the commencement of any works including demolition and excavation. The site management measures are to be

maintained throughout the works, to maintain reasonable levels of public health, safety and amenity. A copy of the Site Management Plan must be kept on site and is to be made available upon request.

10. Photographic Archival Documentation (Minor Works)

Prior to a Construction Certificate being issued, an archival photographic recording of 74-76 Homebush Road, Strathfield is to be prepared to Council's satisfaction. The recording is to be in digital form, or a combination of both, prepared in accordance with Heritage NSW guidelines titled "Photographic Recording of Heritage Items using Film or Digital Capture". One copy of the record is to be submitted to Council to be lodged with Council's Archives.

The form of the recording is to be as follows:

- (a) The Development Application number must be noted on the submitted information.
- (b) Include a summary report detailing the project description, date and authorship of the photographic record, method of documentation and limitations of the photographic record.
- (c) Include written confirmation, issued with the authority of both the applicant and the photographer that Strathfield Council is granted a perpetual non-exclusive licence to make use of the copyright in all images supplied, including the right to make copies available to third parties as though they were Council images. The signatures of both the applicant and the photographer must be included.
- (d) The report is to be submitted on a USB, CD or DVD, in PDF/A format, (created directly from the digital original), with the digital catalogue of images containing the following data for each: DOS title, image subject/description and data photograph was taken.
- (e) The electronic images are to be taken with a minimum 8 megapixel camera, saved as JPEG TIFF or PDF files with a size of approximately 4-6MB, and cross referenced to the digital catalogue sheets and base plans. Choose only images that are necessary to document the process, and avoid duplicate images.

11. Erosion & Sedimentation Control

Erosion and sediment controls must be provided to ensure:

- (a) Compliance with the approved Erosion & Sediment Control Plan
- (b) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval)
- (c) All clean water run-off is diverted around cleared or exposed areas
- (d) Silt fences, stabilised entry/exit points or other devices are installed to prevent sediment from entering drainage systems or waterways
- (e) All erosion and sediment controls are fully maintained for the duration of demolition, excavation and/or development works
- (f) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadway
- (g) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or

similar

- (h) Compliance with [Managing Urban Stormwater – Soils and Construction \(Blue Book\) produced by Landcom 2004.](#)

These measures are to be implemented prior to the commencement of work (including demolition and excavation) and must remain until works are completed and all exposed surfaces are landscaped/sealed.

12. On Site Detention

The submitted stormwater plan has been assessed as a concept plan only. Final detailed plans of the drainage system, prepared by a professional engineer specialising in hydraulic engineering, shall be submitted for approval with the Construction Certificate.

An on-site detention (OSD) facility designed by a professional engineer who specialises in Hydraulic Engineering must be designed, approved and installed. The design must include the computations of the inlet and outlet hydrographs and stage/storage relationships of the proposed OSD using the following design parameters:

- (a) Peak flow rates from the site are to be restricted to a permissible site discharge (PSD) equivalent to the discharge when assuming the site contained a single dwelling, garage, lawn and garden,
- (b) At Annual Recurrence Intervals of 2 years, 10 years and 100 years.

The OSD facility shall be designed to meet all legislated safety requirements and childproof safety fencing around the facility must be provided where the OSD facility is open or above ground when the design peak storage depth is greater than 300mm. A durable metal plate or similar sign is to be placed at the OSD facility and must bear the words:

"BEWARE: This is an on-site detention basin/tank for rainwater which could overflow during heavy storms."

Full details shall accompany the application for the Construction Certificate.

13. Detailed Stormwater Drainage Design

The submitted stormwater plan has been assessed as a concept plan only. A detailed drainage design supported by a catchment area plan and drainage calculations (including a Hydraulic Grade Line Analysis) in accordance with Council's Stormwater Management Code must be submitted with the Construction Certificate application.

14. Engineer's Certificate

A certificate from a professional Engineer specialising in structural engineering certifying the structural adequacy of the existing structure, to support all proposed additional superimposed loads shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

15. Access for Persons with a Disability

Access and sanitary facilities for persons with disabilities must be provided to the premises/building in accordance with the requirements of the Premises Standards, the Building Code of Australia, and AS 1428.1. Details must be submitted with the Construction Certificate Application for approval.

16. Commonwealth Disability (Access to Premises) Standard

The Commonwealth Disability (Access to Premises - Buildings) Standards 2010 (the Premises Standards) applies to all applications (i.e. Construction Certificate). This requires any new building, part of a building and the affected part of the existing building to comply with the Premises Standards, the Building Code of Australia and AS 1428.

17. Acoustic Requirements**Compliance with submitted Acoustic Report**

The Construction Certificate plans shall demonstrate compliance with the Acoustic Report submitted and approved by Council, titled Noise Impact Assessment prepared by Rodney Stevens and dated 2 June 2020.

18. Waste Management Plan

A Waste Management Plan incorporating all requirements in respect of the provision of waste storage facilities, removal of all materials from the site that are the result of site clearing, extraction, and, or demolition works and the designated Waste Management Facility shall be submitted to and approved by the Certifying Authority prior to the issue of any Construction Certificate.

WMP should also indicate how waste education will be provided, in order to minimise waste disposal, contamination and to increase recycling. Educational signage is to be installed in waste rooms and commons areas.

[EPA's Better Practice Guide for Waste Management in Multi-unit Dwellings](#) and [Better Practice Guidelines for Waste Management and Recycling in Commercial and Industrial Facilities](#) should be used to inform design and waste management outcomes in new and existing development.

19. Commercial and Industrial Waste

Appropriate waste and recycling containers and facilities will need to be provided according to the approved Waste Management Plan for all specific end use businesses in accordance with the waste generation rates provided at Part H of Strathfield Council DCP 2005 – Appendix B.

WMP should also provide written evidence of valid contracts for the regular collection and disposal of waste and recyclables generated on the site. The private waste contractor must confirm the frequency of the waste collections (general waste, recycling and bulky goods), and that the size and location of the storage room is suitable for the frequency of the waste collections.

The collection of commercial and industrial waste and recycling must only occur between 6.00am and 8.00pm weekdays and 9.00am and 5.00pm on weekends and public holidays, to avoid noise disruption to the surrounding area. All garbage and recyclable matter must be enclosed in the waste bins with lids completely closed at all times.

Waste education must be provided through signs in common areas indicating how to avoid, reduce, reuse and recycle waste.

Note: Refer to the EPA's [Better Practice Guidelines for Waste Management and Recycling in Commercial and Industrial Facilities](#)

20. Landscape Plans

All landscape works shall be carried out in accordance with the approved landscape plans. The landscaping shall be maintained in accordance with the approved plans in perpetuity.

21. Compliance with Submitted Arborist Report

The recommendations outlined in the Arborist's Report titled Arboricultural Impact Appraisal and Method Statement prepared by Naturally Trees dated 16 July 2020 must be implemented throughout the relevant stages of construction. Details of tree protection measures to be implemented must be detailed and lodged with the Construction Certificate application for approval and shall be in accordance with Section 4 - Australian Standard AS 4970-2009: Protection of trees on development sites.

22. Tree Removal & Replacement

Tree removal

Permission is granted for the removal of the following trees:

Tree No.	Tree species	Number of trees	Location
9, 10, 11, 12 and 15 As stated in the approved Arborist report dated 16 July 2020			

General Tree Removal Requirements

All tree removal shall be carried out by a certified Tree Surgeon/Arborist to ensure that removal is undertaken in a safe manner and complies with the AS 4373-2007 - Pruning of Amenity Trees and Amenity Tree Industry Code of Practice (Safework NSW, August 1998).

Tree Replacement

All trees permitted to be removed by this consent and shall be replaced with 3 new trees in the front and rear setback of the site, capable of growing to a potential mature height of a minimum 15 metre. The trees shall be selected from Council's Recommended Tree List. **NOTE: This can include the new tree plantings required along the deleted driveway area.**

Replacement trees shall be a minimum 100 litre container size. Trees are to conform to the NATSPEC guide and Guide for assessing the quality of and purchasing of landscape trees by Ross Clarke, 2003. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting; and shall be maintained until maturity.

All trees are to be staked and tied with a minimum of three (3) hardwood stakes. Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.

Soil conditioner/fertilizer/moisture retention additive/s are to be applied in accordance with manufacturer's recommendations, and mixed into the backfilling soil after planting tree/s.

A minimum 75mm depth of organic mulch shall be placed within an area 0.5m from the base of the tree.

Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

PRIOR TO THE COMMENCEMENT OF WORK (INCLUDING DEMOLITION & EXCAVATION)

23. Demolition & Asbestos

The demolition work shall comply with the provisions of Australian Standard AS2601:2001 – Demolition of Structures, NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#). The work plans required by AS2601:2001 shall be accompanied by a written statement by a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the safety statement shall be submitted to the PCA prior to the commencement of works.

For demolition work which involves the removal of asbestos, the asbestos removal work must be carried out by a licensed asbestos removalist who is licensed to carry out the work in accordance with the NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#) unless specified in the Act and/or Regulation that a license is not required.

All demolition work including the removal of asbestos, shall be undertaken in accordance with the [Demolition Code of Practice](#) (NSW Work Cover July 2015)

Note: Copies of the Act, Regulation and Code of Practice can be downloaded free of charge from the SafeWork NSW website: www.SafeWork.nsw.gov.au.

24. Demolition Notification Requirements

The following notification requirements apply to this consent:

- (a) The developer /builder must notify adjoining residents five (5) working days prior to demolition. Such notification is to be a clearly written note giving the date demolition will commence, contact details of the developer/builder, licensed asbestos demolisher and the appropriate regulatory authority. Notification is to be placed in the letterbox of every premises (including every residential flat or unit, if any) either side and immediately at the rear of the demolition site.
- (b) Five (5) working days prior to demolition, the developer/builder is to provide written notification to Council advising of the demolition date, details of the SafeWork licensed asbestos demolisher and the list of residents advised of the demolition.
- (c) On demolition sites where buildings to be demolished contain asbestos, a standard commercially manufactured sign containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm is to be erected in a prominent visible position (from street frontage) on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos material has been removed from the site to an approved waste facility.

25. Demolition Work Involving Asbestos Removal

Work involving bonded asbestos removal work (of an area of more than 10 square metres) or friable asbestos removal work must be undertaken by a person who carries on a

business of such removal work in accordance with a licence under clause 458 of the [Work Health and Safety Regulation 2011](#).

26. **Materials for Making Good**

New materials for making good and repairs, are to match the existing in terms of colours, finishes, sizes, profile and properties.

27. **Dial Before You Dig**

The applicant shall contact “Dial Before You Dig on 1100” to obtain a Service Diagram prior to the issuing of the Construction Certificate. The sequence number obtained from “Dial Before You Dig” shall be forwarded to Council’s Engineers for their records.

DURING CONSTRUCTION

28. **Site Sign – Soil & Erosion Control Measures**

Prior to the commencement of works (including demolition and excavation), a durable site sign, issued by Council in conjunction with this consent, must be erected in a prominent location on site. The site sign warns of the penalties which apply to pollution, storing materials on road or footpath and breaches of the conditions relating to erosion and sediment controls. The sign must remain in a prominent location on site up until the completion of all site and building works.

29. **Hours of Construction for Demolition and Building Work**

Any work activity or activity associated with the development consent that requires the use of any tools (including hand tools) or any power operated plant and machinery that creates noise on or adjacent to the site shall not be performed, or permitted to be performed, except between the hours of 7.00 am to 5.00 pm, Monday to Friday and 8:00am to 1:00pm on Saturdays. No work or ancillary activity is permitted on Sundays, or Public Holidays.

Where the development involves the use of jack hammers/rock breakers and the like, or other heavy machinery, such equipment may only be used between the hours of 7:00am to 5:00pm Monday to Friday only.

Note: A penalty infringement notice may be issued for any offence.

30. **Ground Levels and Retaining Walls**

The ground levels of the site shall not be excavated, raised or filled, or retaining walls constructed on the allotment boundary, except where indicated on approved plans or approved by Council.

PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

31. **Completion of Landscape Works**

At the completion of all works, a certificate is to be submitted to the Principal Certifying Authority from a qualified Landscape and/or Arboricultural Consultant certifying that the work has been completed in accordance with the approved Landscape Plan and that a maintenance program has been established.

32. Restriction to User and Positive Covenant for On-Site Detention Facility

Prior to the issue of any Occupation Certificate, the applicant shall register a Positive Covenant and a Restriction as to User under section 88E and or section 88B of the Conveyancing Act as appropriate in favour of Council, ensuring the ongoing retention, maintenance and operation of the stormwater facility (on-site detention, pump-out, charged lines, water sensitive urban design, surface flow path, finished pavement and ground levels etc.).

Where any drainage line or service conduit is to traverse any property other than that which it serves, an appropriate easement will be required. In this case, the applicant shall register an easement no less than 1200mm wide over the proposed drainage line or service concurrently with any subdivision registration.

The wording on the 88E and or 88B Instrument is to make reference to the Council file where the Construction plans and the Work As Executed (as built), plans are held. Typical wording can be obtained from Council's Specification for the Management of Stormwater document.

33. Stormwater Certification of the Constructed Drainage Works (Minor)

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

34. Vehicular Crossing - Minor Development

The vehicular crossing and/or footpath works shall be constructed by a private contractor at the expense of the applicant, in accordance with the Works Permit Approval issued by Council's Civic & Urban Services and in accordance with Council's Driveway Specifications.

Any existing vehicular crossing and/or laybacks which are redundant must be removed. The kerb and gutter, any other footpath and turf areas shall be restored at the expense of the applicant and in accordance with Council's Driveway Specifications.

The work must be completed before the issue of an Occupation Certificate.

35. Fire Safety Certificate before Occupation or Use

In accordance with Clause 153 of the [Environmental Planning and Assessment Regulation 2000](#), on completion of building works and prior to the issue of an Occupation Certificate, the owner must cause the issue of a Final Fire Safety Certificate in accordance with Clause 170 of the aforesaid Regulation. The Fire Safety Certificate must be in the form or to the effect of Clause 174 of the [Environmental Planning and Assessment Regulation, 2000](#). In addition, in relation to each essential fire or other safety measure implemented in the building or on the land on which the building is situated, such a Certificate is to state:

- (a) That the measure has been assessed by a person (chosen by the owner of the building) who is properly qualified to do so.
- (b) That as at the date of the assessment the measure was found to be capable of functioning at a standard not less than that required by the attached Schedule.

A copy of the certificate is to be given by the applicant to the Commissioner of Fire & Rescue NSW and a further copy is to be displayed in a frame and fixed to a wall inside the building's main entrance.

36. Maximum Number of Persons

The building shall not exceed the maximum capacity numbers at any given time as prescribed below:

Description of Building Portion "Scheduled Area(s)"	Approved Capacity/Patronage
Building (including office space and learning areas)	10 staff / parents 25 students
Total	35 persons

37. Acoustic Certification

Prior to the issue of any Occupation Certificate, a suitably qualified acoustic consultant shall certify that the operation of the premises and plant equipment shall not give rise to a sound pressure level at any affected premises that exceeds the acoustic criteria established by the Acoustic Report required by a condition of this consent. The development shall at all times comply with these noise levels post occupation.

38. Acoustic Compliance

Prior to the issue of any Occupation Certificate, a report prepared by a suitably qualified acoustic consultant must be submitted to the PCA certifying that the construction has incorporated the recommendations in the DA Acoustic Report titled Noise Impact Assessment prepared by Rodney Stevens Acoustics and dated 2 June 2020.

PRIOR TO THE ISSUE OF THE SUBDIVISION CERTIFICATE

Nil

OPERATIONAL CONDITIONS (ON-GOING)

39. Noise Control

The use of the premises must not give rise to the transmission of offensive noise to any place of different occupancy. Offensive noise is defined in the [Protection of the Environment Operations Act 1997](#) (as amended).

40. Schedule of Existing Fire Measures to be Maintained

The following statutory safety measures are existing and shall be fully maintained in accordance with the approved standard and inspected annually:

- (a) Access panels, door and hoppers to fire resisting shafts - minimum standard AS 1905.1 - 2015.
- (b) Automatic fail safe devices - minimum standard Part D of BCA.
- (c) Automatic fire detection and alarm systems - minimum standard AS 1670.2015, and AS1670.3 & 4 – 2004

- (d) Automatic fire suppression systems - minimum standard AS 2118.1 – 2006.
- (e) Emergency lighting - minimum standard AS 2293.1 - 2005.
- (f) Emergency lifts - minimum standard AS 1735.1,2,11, 3, 7, 8, 12, 14, 15, and 16 (as currently applicable).
- (g) Emergency warning and intercommunication systems - minimum standard AS 4428.4 – Fire detection, warning, control and intercom systems.
- (h) Exit signs - minimum standard AS 2293.1 - 2005.
- (i) Fire control centres and rooms - minimum standard BCA.
- (j) Fire dampers - minimum standard AS 1682.1 & AS 1682.2 - 2015.
- (k) Fire doors - minimum standard AS 1905.2 - 2005.
- (l) Fire hydrant systems - minimum standard AS 2419.1 -2005.
- (m) Fire seals protecting openings in fire resisting components of the building - minimum standard Part C of BCA.1
- (n) Fire shutters - minimum standard AS 1905.2. - 2005.
- (o) Fire windows - minimum standard AS 1905.1- 2015.
- (p) Hose reel systems - minimum standard AS 2441 - 2005.
- (q) Lightweight construction - minimum standard Part C of BCA.
- (r) Mechanical air handling systems - minimum standard AS 1668.2 - 2012.
- (s) Perimeter vehicle access for emergency vehicles - minimum standard Part C of BCA.1
- (t) Portable fire extinguishers - minimum standard AS 2444 - 2001.
- (u) Safety curtains in proscenium openings - minimum standard Part H of BCA.
- (v) Smoke and heat vents - minimum standard AS 2665. - 2001.
- (w) Smoke dampers - minimum standard AS 1682.1 and 2 - 2015.
- (x) Smoke detectors and heat detectors - minimum standard AS 3786 - 2014 and AS 1670.1 - 2015.
- (y) Smoke doors - minimum standard AS 1905.1 -2015.
- (z) Solid core doors - minimum standard Part C of BCA.
- (aa) Stand-by power systems - Spec. G. 3.8 of BCA and AS 2665. - 2001.
- (bb) Wall wetting sprinkler and drencher systems - minimum standard AS 2118.2. -2010.
- (cc) Warning and operations signs - minimum standard is BCA.1

OPERATIONAL REQUIREMENTS UNDER THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979**41. Appointment of a PCA**

The erection of a building must not commence until the applicant has:

- (a) Appointed a PCA for the building work; and
- (b) If relevant, advised the PCA that the work will be undertaken as an Owner -Builder.

If the work is not going to be undertaken by an Owner - Builder, the applicant must:

- (c) Appoint a Principal Contractor to undertake the building work. If residential building work (within the meaning of the [Home Building Act 1989](#)) is to be undertaken, the Principal Contractor must be a holder of a contractor licence; and
- (d) Notify the PCA of the details of any such appointment; and
- (e) Notify the Principal Contractor of any critical stage inspections or other inspections that are required to be carried out in respect of the building work.

42. Occupation Certificate

A person must not commence occupation or use of the whole or any part of a new building unless an Occupation Certificate has been issued in relation to the building or part.

PRESCRIBED CONDITIONS**43. Clause 98 – Building Code of Australia & Home Building Act 1989**

Requires all building work to be carried out in accordance with the Building Code of Australia. In the case of residential building work to which the [Home Building Act 1989](#) relates, there is a requirement for a contract of insurance to be in force before any work commences.

44. Clause 98A – Erection of Signs

Requires the erection of signs on site and outlines the details which are to be included on the sign. The sign must be displayed in a prominent position on site and include the name and contact details of the PCA and the Principal Contractor.

ADVISORY NOTES**i. Review of Determination**

Section 8.2 of the Environmental Planning and Assessment Act confers on an applicant who is dissatisfied with the determination of the application the right to lodge an application with Council for a review of such determination. Any such review must however be completed within 6 months from its determination. Should a review be contemplated sufficient time should be allowed for Council to undertake public notification and other processes involved in the review of the determination.

Note: review provisions do not apply to Complying Development, Designated Development, State Significant Development, Integrated Development or any application determined by

the Sydney East Planning Panel or the Land & Environment Court.

ii. **Appeal Rights**

Division 8.3 (Reviews and appeals) Part 8 of the Environmental Planning and Assessment Act 1979 confers on an applicant who is dissatisfied with the determination of the application a right of appeal to the Land and Environment Court of New South Wales.

iii. **Lapsing of Consent**

This consent will lapse unless the development is physically commenced within 5 years from the Date of Operation of this consent, in accordance with Section 4.53 of the Environmental Planning and Assessment Act 1979 as amended.

iv. **Access to NSW Legislations (Acts, Regulations and Planning Instruments)**

NSW legislation can be accessed free of charge at www.legislation.nsw.gov.au

v. **Long Service Levy**

The Long Service Corporation administers a scheme which provides a portable long service benefit for eligible workers in the building and construction industry in NSW. All benefits and requirements are determined by the Building and Construction Industry Long Service Payments Act 1986. More information about the scheme and the levy amount you are required to pay to satisfy a condition of your consent can be found at <http://www.longservice.nsw.gov.au>.

The required Long Service Levy payment can be direct to the Long Service Corporation via their web site <https://online.longservice.nsw.gov.au/bci/levy>. Payments can only be processed on-line for the full levy owing and where the value of work is between \$25,000 and \$6,000,000. Payments will be accepted for amounts up to \$21,000, using either MasterCard or Visa.

vi. **Disability Discrimination Act**

This application has been assessed in accordance with the [Environmental Planning and Assessment Act 1979](#). No guarantee is given that the proposal complies with the [Disability Discrimination Act 1992](#). The applicant is responsible to ensure compliance with this and other anti-discrimination legislation. The [Disability Discrimination Act 1992](#) covers disabilities not catered for in the minimum standards called up in the Building Code of Australia which refers to AS1428.1-Design for Access and Mobility.

vii. **Site Safety Fencing**

Site fencing must be erected in accordance with SafeWork Guidelines, to exclude public access to the site throughout the demolition and/or construction work, except in the case of alterations to an occupied dwelling. The fencing must be erected before the commencement of any work and maintained throughout any demolition and construction work.

A demolition licence and/or a high risk work license may be required from SafeWork NSW (see www.SafeWork.nsw.gov.au).

viii. **Noise**

Council will generally enforce noise related conditions in accordance with the Noise Guide for Local Government (<http://www.environment.nsw.gov.au/noise/nlgq.htm>) and the

Industrial Noise Guidelines (<http://www.environment.nsw.gov.au/noise/industrial.htm>) publish by the Department of Environment and Conservation. Other state government authorities also regulate the [Protection of the Environment Operations Act 1997](#).

Useful links relating to Noise:

- (a) Community Justice Centres—free mediation service provided by the NSW Government (www.cjc.nsw.gov.au).
- (b) Department of Environment and Conservation NSW, Noise Policy Section web page (www.environment.nsw.gov.au/noise).
- (c) New South Wales Government Legislation home page for access to all NSW legislation, including the *Protection of the Environment Operations Act 1997* and the *Protection of the Environment Noise Control Regulation 2000* (www.legislation.nsw.gov.au).
- (d) Australian Acoustical Society—professional society of noise-related professionals (www.acoustics.asn.au/index.php).
- (e) Association of Australian Acoustical Consultants—professional society of noise related professionals (www.aaac.org.au).
- (f) Department of Gaming and Racing - (www.dgr.nsw.gov.au).

ix **Acoustical Engineer Contacts & Reference Material**

Further information including lists of Acoustic Engineers can be obtained from:

- (a) Australian Acoustical Society—professional society of noise-related professionals (www.acoustics.asn.au)
- (b) Association of Australian Acoustical Consultants—professional society of noise related professionals (www.aaac.org.au)
- (c) NSW Industrial Noise Policy – Office of Environment & Heritage (www.environment.nsw.gov.au)

RESOLUTION

This Development Application is **APPROVED** subject to the recommended conditions of consent as amended by the Panel.

FOR: Paul Stein, Eric Armstrong, David Starr, Jan Murrell

AGAINST: Nil

Reasons: the Panel generally agrees with the Planning Officers report but has made some amendments to the recommended conditions of consent.

**** End Minutes - Report No. 34****

TO: Strathfield Local Planning Panel Meeting - 3 September 2020
REPORT: SLPP – Report No. 35
SUBJECT: DA2020/093 - 25 ROCHESTER STREET - LOT 22 DP 527225
DA NO. 2020/093

RECOMMENDATION

That Development Application No. DA2020/093 for construction of a Studio Apartment fronting a rear lane and defined as shop top housing at 25 Rochester Street, Homebush be **APPROVED**, subject to the following conditions:

The following conditions of consent are imposed for the following reasons:

- (a) To ensure compliance with the terms of the relevant Environmental Planning Instrument and/or Building Code of Australia and/or Council's codes, policies and specifications.
- (b) To protect the environment.
- (c) To ensure that there is no unacceptable impact on the amenity of the area, or to private and public property.
- (d) It is in the public interest.

1. Approved Plans & Documentation

The development must be implemented in accordance with the approved plans and supporting documentation listed below which have been endorsed by Council's approved stamp, except where marked up on the plans and/or amended by conditions of this consent:

Description	Reference No.	Date	Revision	Prepared by
Site Plan	02 SPA	1/7/2020	A	apwdesign
Concept Stormwater Drainage Plan	03 CSDPA	1/7/2020	A	apwdesign
Demolition Plan Ground Floor	04 491 DP GFA	1/7/2020	A	apwdesign
Demolition Plan First Floor	05 491 DP FFA	1/7/2020	A	apwdesign
Proposed Ground Floor	06 491 PGFA	1/7/2020	A	apwdesign
Proposed First Floor	07 491 PFFA	1/7/2020	A	apwdesign
Elevations	08 491 E1A	1/7/2020	A	apwdesign

Elevations	09 491 E2A	1/7/2020	A	apwdesign
Sections	10 491 S1A	1/7/2020	A	apwdesign
Sections	10 491 S2A	1/7/2020	A	apwdesign
Materials and Finishes	01 491 MF	1/7/2020	A	apwdesign
Plan showing detail and levels of lot 22 in DP 527225 at no.25 Rochester Street, Homebush	2019	31/03/2020	-	3D Surveying
Waste Management Plan For the Proposal Addition Shop Top Housing at LOT 22, DP 52 7225, No 25 Rochester, Street, HOMEBUSH, NSW 2129	-	-	-	apwdesign

2. Building Height

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) 15.126m AHD to the roof ridge of the proposed dwelling.

SEPARATE APPROVALS REQUIRED UNDER OTHER LEGISLATION

3. Section 138 Roads Act 1993 and Section 68 Local Government Act 1993

Unless otherwise specified by a condition of this consent, this Development Consent does not give any approval to undertake works on public infrastructure.

Separate approval is required under Section 138 of the [Roads Act 1993](#) and/or Section 68 of the [Local Government Act 1993](#) for any of the following activities carried out in, on or over a public road (including the footpath) listed below.

An application is required to be lodged and approved prior to the commencement of any of the following works or activities;

- (a) Placing or storing materials or equipment;

- (b) Placing or storing waste containers or skip bins;
- (c) Erecting a structure or carrying out work
- (d) Swinging or hoisting goods over any part of a public road by means of a lift, crane or the like;
- (e) Pumping concrete from a public road;
- (f) Pumping water from the site into the public road;
- (g) Constructing a vehicular crossing or footpath;
- (h) Establishing a “works zone”;
- (i) Digging up or disturbing the surface of a public road (e.g. Opening the road for the purpose of connections to utility providers);
- (j) Stormwater & ancillary works in the road reserve; and
- (k) Stormwater & ancillary to public infrastructure on private land
- (l) If any excavation is to be supported by the use of below ground (cable) anchors that are constructed under Council’s roadways/footways.

These separate activity approvals must be obtained and evidence of the approval provided to the Certifying Authority prior to the issue of the Construction Certificate.

The relevant Application Forms for these activities can be downloaded from Council’s website www.strathfield.nsw.gov.au. For further information, please contact Council’s Customer Service Centre on (02) 9748 9999.

REQUIREMENTS OF CONCURRENCE, INTEGRATED & OTHER GOVERNMENT AUTHORITIES

4. Sydney Water – Tap in™

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water’s sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to ‘Plumbing, building and developing’ section of Sydney Water’s web site at www.sydneywater.com.au then see ‘Building’, or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

5. Required Design Changes

The following changes are required to be made and shown on the Construction Certificate plans:

Northern elevation	The portion of the steel cladding adjoining the private open space (patio) is to be deleted.
--------------------	--

Changes to Existing Ground Floor Dwelling The applicant shall install on the roof of the existing ground floor unit a twister style ventilation fan to improve the circulation within the dwelling.

Sensor Light in Rear Lane The applicant to install and maintain a movement sensor flood light over the rear pedestrian door of the rear lane

6. Fees to be Paid

The fees listed in the table below must be paid in accordance with the conditions of this consent and Council's adopted Fees and Charges applicable at the time of payment (available at www.strathfield.nsw.gov.au).

Payments must be made prior to the issue of the Construction Certificate or prior to the commencement of work (if there is no associated Construction Certificate).

Please contact council prior to the payment of s7.11 or s7.12 Contributions to determine whether the amounts have been indexed from that indicated below in this consent and the form of payment that will be accepted by Council.

A summary of the fees to be paid are listed below:

Fee Type	Fee
GENERAL FEES	
Long Service Levy (to Long Service Corporation)	\$525
Or, provide evidence of Payment direct to the Long Service Corporation. See https://portal.longservice.nsw.gov.au/bci/levy/	
Security Damage Deposit	\$5,200
Administration Fee for Damage Deposit	\$127.00
STRATHFIELD 7.11 DIRECT CONTRIBUTIONS PLAN	
Provision of Community Facilities	\$1,524.70
Provision of Major Open Space	\$6,936.91
Provision of Local Open Space	\$2,377.43
Provision Roads and traffic Management	\$597.20
Administration	\$131.47
TOTAL	\$11,567.71

General Fees

The fees and charges above are subject to change and are as set out in the version of Council's Schedule of Fees and Charges or as required by other Government Authorities, applicable at the time of payment.

Development Contributions

The Section 7.11 contribution (s94) is imposed to ensure that the development makes adequate provision for the demand it generates for public amenities and public services within the area.

A Section 7.12 contribution has been levied on the subject development pursuant to the Strathfield Section 94A Indirect Development Contributions Plan.

Indexation

The above contributions will be adjusted at the time of payment to reflect changes in the cost of delivering public amenities and public services, in accordance with the indices provided by the relevant Development Contributions Plan.

Timing of Payment

The contribution must be paid and receipted by Council:

- Prior to the consent being acted upon.

Further Information

A copy of the current Development Contributions Plans may be inspected at Council's Customer Service Centre at 65 Homebush Road, Strathfield or on Council's website www.strathfield.nsw.gov.au.

7. **Schedule of External Materials, Colours and Finishes**

The external CC8035 - The balustrade and railings are to be of a federation period form to be approved by the Heritage Advisor prior to issuing a Construction Certificate.

It is recommended that reference be made to the book "Colour Schemes for Old Australian Houses" by Ian Evans, Clive Lucas and Ian Stapleton.

8. **Damage Deposit – Minor Works**

In order to insure against damage to Council property the following is required:

- (a) Pay Council, before the issue of the Construction Certificate, a damage security deposit for the cost of making good any damage caused to any Council property as a result of the development: **\$5,200.**
- (b) Pay Council, before the issue of the Construction Certificate, a non-refundable administration fee to enable assessment of any damage and repairs where required: **\$127.**

At the completion of work Council will inspect the public works, and the damage deposit will be refunded in full upon completion of work where no damage occurs. Otherwise the amount will be either forfeited or partly refunded according to the amount of damage.

9. Site Management Plan**Minor Development**

A Site Management Plan detailing all weather access control points, sedimentation controls, waste management plans, fencing, builder's site sheds office, amenities, materials storage and unloading arrangements must be submitted with the application for the Construction Certificate.

The site management measures are to be implemented prior to the commencement of any works including demolition and excavation. The site management measures are to be maintained throughout the works, to maintain reasonable levels of public health, safety and amenity. A copy of the Site Management Plan must be kept on site and is to be made available upon request.

10. BASIX Commitments

The approved BASIX Certificate shall be submitted to the Accredited Certifier with the application for a Construction Certificate.

All measures and commitments as detailed in the BASIX Certificate No. 1080736S must be implemented on the plans lodged with the application for the Construction Certificate.

11 Erosion & Sedimentation Control

Erosion and sediment controls must be provided to ensure:

- (a) Compliance with the approved Erosion & Sediment Control Plan
- (b) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval)
- (c) All clean water run-off is diverted around cleared or exposed areas
- (d) Silt fences, stabilised entry/exit points or other devices are installed to prevent sediment from entering drainage systems or waterways
- (e) All erosion and sediment controls are fully maintained for the duration of demolition, excavation and/or development works
- (f) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadway
- (g) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar
- (h) Compliance with [Managing Urban Stormwater – Soils and Construction \(Blue Book\) produced by Landcom 2004](#).

These measures are to be implemented prior to the commencement of work (including demolition and excavation) and must remain until works are completed and all exposed surfaces are landscaped/sealed.

12. Stormwater System

The submitted stormwater plan has been assessed as a concept plan only. Final detailed plans of the drainage system in accordance with Council stormwater management code and

AS/NZS 3500.3: 2015 (as amended), prepared by a professional engineer specialising in hydraulic engineering, shall be submitted for approval with the Construction Certificate.

13. Detailed Stormwater Drainage Design

The submitted stormwater plan has been assessed as a concept plan only. A detailed drainage design supported by a catchment area plan and drainage calculations (including a Hydraulic Grade Line Analysis) in accordance with Council's Stormwater Management Code must be submitted with the Construction Certificate application.

14. Drainage System – Maintenance of Existing System

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

15. Engineer's Certificate

A certificate from a professional Engineer specialising in structural engineering certifying the structural adequacy of the existing structure, to support all proposed additional superimposed loads shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

16. Fire Safety Measures

Prior to the issue of a construction certificate a list of the existing and proposed essential fire safety measures that are to be provided in relation to the land and any building on the land as a consequence of the building work must accompany an application for a construction certificate, which is required to be submitted to either Council or a PCA. Such list must also specify the minimum standard of performance for each essential fire safety measure included in the list. The Council or PCA will then issue a Fire Safety Schedule for the building.

17. Structural Details

Engineer's details prepared by a practising Structural Engineer being used to construct all reinforced concrete work, structural beams, columns & other structural members. The details are to be submitted to the Principal Certifying Authority for approval prior to construction of the specified works.

A copy shall be forwarded to Council where Council is not the PCA.

18. Total Conformity with the BCA – Clause 93 and 94 EP& A Regulation 2000

Pursuant to Clause [93 AND/OR 94] of the Environmental Planning and Assessment Regulation 2000, the existing building must be brought into total conformity with the Building Code of Australia. In this regard, construction plans that demonstrate compliance with the Building Code of Australia must be submitted to the Certifying Authority with the Construction Certificate application for approval.

Should there be any non-compliance, and an alternative method of fire protection and structural capacity is proposed, a detailed report, plans and supporting documents prepared by an appropriately accredited and qualified fire consultant having specialist qualifications in

fire engineering must be submitted, justifying the non-compliances.

PRIOR TO THE COMMENCEMENT OF WORK (INCLUDING DEMOLITION & EXCAVATION)

19. Demolition & Asbestos

The demolition work shall comply with the provisions of Australian Standard AS2601:2001 – Demolition of Structures, NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#). The work plans required by AS2601:2001 shall be accompanied by a written statement by a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the safety statement shall be submitted to the PCA prior to the commencement of works.

For demolition work which involves the removal of asbestos, the asbestos removal work must be carried out by a licensed asbestos removalist who is licensed to carry out the work in accordance with the NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#) unless specified in the Act and/or Regulation that a license is not required.

All demolition work including the removal of asbestos, shall be undertaken in accordance with the [Demolition Code of Practice](#) (NSW Work Cover July 2015)

Note: Copies of the Act, Regulation and Code of Practice can be downloaded free of charge from the SafeWork NSW website: www.SafeWork.nsw.gov.au.

20. Demolition Notification Requirements

The following notification requirements apply to this consent:

- (a) The developer /builder must notify adjoining residents five (5) working days prior to demolition. Such notification is to be a clearly written note giving the date demolition will commence, contact details of the developer/builder, licensed asbestos demolisher and the appropriate regulatory authority. Notification is to be placed in the letterbox of every premises (including every residential flat or unit, if any) either side and immediately at the rear of the demolition site.
- (b) Five (5) working days prior to demolition, the developer/builder is to provide written notification to Council advising of the demolition date, details of the SafeWork licensed asbestos demolisher and the list of residents advised of the demolition.
- (c) On demolition sites where buildings to be demolished contain asbestos, a standard commercially manufactured sign containing the words “DANGER ASBESTOS REMOVAL IN PROGRESS” measuring not less than 400mm x 300mm is to be erected in a prominent visible position (from street frontage) on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos material has been removed from the site to an approved waste facility.

21. Demolition Work Involving Asbestos Removal

Work involving bonded asbestos removal work (of an area of more than 10 square metres) or friable asbestos removal work must be undertaken by a person who carries on a business of such removal work in accordance with a licence under clause 458 of the [Work Health and Safety Regulation 2011](#).

22. Structural Integrity of Retained Building Elements

Prior to a commencement of demolition, excavation or construction work, a report or

certification from a practicing structural engineer experienced in dealing with heritage buildings must be submitted to and approved by Council's Heritage Advisor. The report must explain how the retained building elements, such as building facades or chimneys are to be retained, supported and not undermined by the proposed development and give details of any intervention or retrofitting needed.

23. **Dial Before You Dig**

The applicant shall contact "Dial Before You Dig on 1100" to obtain a Service Diagram prior to the issuing of the Construction Certificate. The sequence number obtained from "Dial Before You Dig" shall be forwarded to Council's Engineers for their records.

Registered Surveyors Report - During Development Work

A report must be submitted to the PCA at each of the following applicable stages of construction:

- (a) Set out before commencing excavation.
- (b) Floor slabs or foundation wall, before formwork or commencing brickwork.
- (c) Completion of Foundation Walls - Before any construction of flooring, detailing the location of the structure relative to adjacent boundaries and floor levels relative to the datum shown on the approved plans.
- (d) Completion of Floor Slab Formwork - Before pouring of concrete/walls construction, detailing the location of the structure relative to adjacent boundaries and floor levels relative to the datum shown on the approved plans. In multi-storey buildings a further survey must be provided at each subsequent storey.
- (e) Completion of any Pool Formwork - Before concreting of pool shell, detailing the location of the pool relative to the adjacent boundaries and its height relative to the datum shown on the approved plans.
- (f) Completion of any Roof Framing - Before roof covered detailing eaves/gutter setback from boundaries.
- (g) Completion of all Work - Detailing the location of the structure (including eaves/gutters) relative to adjacent boundaries and its height relative to the datum shown on the approved plans. A final Check Survey must indicate the reduced level of the main ridge.

Work must not proceed beyond each stage until the PCA is satisfied that the height and location of the building is proceeding in accordance with the approved plans.

DURING CONSTRUCTION

24. **Site Sign – Soil & Erosion Control Measures**

Prior to the commencement of works (including demolition and excavation), a durable site sign, issued by Council in conjunction with this consent, must be erected in a prominent location on site. The site sign warns of the penalties which apply to pollution, storing materials on road or footpath and breaches of the conditions relating to erosion and sediment controls. The sign must remain in a prominent location on site up until the completion of all site and building works.

24. **Hours of Construction for Demolition and Building Work**

Any work activity or activity associated with the development consent that requires the use of any tools (including hand tools) or any power operated plant and machinery that creates

noise on or adjacent to the site shall not be performed, or permitted to be performed, except between the hours of 7.00 am to 5.00 pm, Monday to Friday and 8:00am to 1:00pm on Saturdays. No work or ancillary activity is permitted on Sundays, or Public Holidays.

Where the development involves the use of jack hammers/rock breakers and the like, or other heavy machinery, such equipment may only be used between the hours of 7:00am to 5:00pm Monday to Friday only.

Note: A penalty infringement notice may be issued for any offence.

26. Ground Levels and Retaining Walls

The ground levels of the site shall not be excavated, raised or filled, or retaining walls constructed on the allotment boundary, except where indicated on approved plans or approved by Council.

27. Obstruction of Road or Footpath

The use of the road or footpath for the storage of any building materials, waste materials, temporary toilets, waste or skip bins, or any other matter is not permitted unless separately approved by Council under Section 138 of the [Roads Act 1993](#) and/or under Section 68 of the [Local Government Act 1993](#). Penalty infringement Notices may be issued for any offences and severe penalties apply.

28. Construction Management Plan

The owner/applicant is to ensure that the approved Construction Traffic management Plan is to be strictly complied with and kept on site at all times during construction works.

PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

29. BASIX Certificate

All energy efficiency measures as detailed in the approved BASIX Certificate in the plans approved with the Development Consent, must be implemented before issue of any Occupation Certificate.

30. BASIX Compliance Certificate

A Compliance Certificate must be provided to the PCA regarding the implementation of all energy efficiency measures as detailed in the approved BASIX Certificate before any Occupation Certificate is issued.

31. Stormwater Certification of the Constructed Drainage Works (Minor)

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

32. Noise Impact Assessment

Preparation of an acoustic assessment, by a suitably qualified acoustic consultant, that demonstrates LAeq levels are achieved in accordance with the EPAs Noise Policy for Industry is to be undertaken and provided to the PCA.

33. Post Construction Dilapidation Report – Private Land

At the completion of the construction works, a suitably qualified person is to be engaged to prepare a post-construction dilapidation report. This report is to ascertain whether the construction works associated with the subject development created any structural damage to the following adjoining premises:

- (a) 23 Rochester Street Homebush (Lot 1 DP 1626)
- (b) 27 Rochester Street (Lot 23 DP 527225)

The report is to be prepared at the expense of the applicant and submitted to the PCA prior to the issue of the Occupation Certificate. In ascertaining whether adverse structural damage has occurred to the adjoining premises, the PCA, must compare the post-construction dilapidation report with the pre-construction dilapidation report required by conditions in this consent.

Evidence confirming that a copy of the post-construction dilapidation report was delivered to the adjoining properties subject of the dilapidation

PRIOR TO THE ISSUE OF THE SUBDIVISION CERTIFICATE

Nil

OPERATIONAL CONDITIONS (ON-GOING)

Nil

OPERATIONAL REQUIREMENTS UNDER THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979**34. Requirement for a Construction Certificate**

The erection of a building must not commence until a Construction Certificate has been issued.

35. Appointment of a PCA

The erection of a building must not commence until the applicant has:

- (a) Appointed a PCA for the building work; and
- (b) If relevant, advised the PCA that the work will be undertaken as an Owner -Builder.

If the work is not going to be undertaken by an Owner - Builder, the applicant must:

- (c) Appoint a Principal Contractor to undertake the building work. If residential building work (within the meaning of the [Home Building Act 1989](#)) is to be undertaken, the Principal Contractor must be a holder of a contractor licence; and
- (d) Notify the PCA of the details of any such appointment; and
- (e) Notify the Principal Contractor of any critical stage inspections or other inspections that are required to be carried out in respect of the building work.

36. Notification of Critical Stage Inspections

No later than two days before the building work commences, the PCA must notify:

- (a) The consent authority and the Council (if not the consent authority) of his or her appointment; and
- (b) The applicant of the critical stage inspections and other inspections that are to be carried out with respect to the building work.

36. Notice of Commencement

The applicant must give at least two days notice to the Council and the PCA of their intention to commence the erection of a building.

37. Critical Stage Inspections

The last critical stage inspection must be undertaken by the PCA. The critical stage inspections required to be carried out vary according to Building Class under the Building Code of Australia and are listed in Clause 162A of the [Environmental Planning and Assessment Regulation 2000](#).

38. Notice to be Given Prior to Critical Stage Inspections

The principal contractor for a building site, or the owner-builder, must notify the PCA at least 48 hours before each required inspection needs to be carried out.

39. Occupation Certificate

A person must not commence occupation or use of the whole or any part of a new building unless an Occupation Certificate has been issued in relation to the building or part.

PRESCRIBED CONDITIONS**40. Clause 97A – BASIX Commitments**

This Clause requires the fulfilment of all BASIX Commitments as detailed in the BASIX Certificate to which the development relates.

41. Clause 98 – Building Code of Australia & Home Building Act 1989

Requires all building work to be carried out in accordance with the Building Code of Australia. In the case of residential building work to which the [Home Building Act 1989](#) relates, there is a requirement for a contract of insurance to be in force before any work commences.

42. Clause 98A – Erection of Signs

Requires the erection of signs on site and outlines the details which are to be included on the sign. The sign must be displayed in a prominent position on site and include the name and contact details of the PCA and the Principal Contractor.

RESOLUTION

This Development Application is **APPROVED** subject to the recommended conditions of consent as amended by the Panel.

FOR: Paul Stein, Jan Murrell, Eric Armstrong, David Starr

AGAINST: Nil

Reasons: The Panel generally agrees with the Planning Officers report and has added some additional conditions to improve the development.

**** End Minutes - Report No. 35****